

teasleyck
12/23/2005
c:\projects\94964d\03502pa.dgn

SUMMARY OF QUANTITIES

CONTRACT NO. 94964				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	13B-1&13B-2	MARION	78	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		DUMS CREEK		SKILLET FORK CREEK	
				X071-2A	SFTY-3N	X071-2A	SFTY-3N
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	4		4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1258	729		529	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18	10		8	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1240	625		615	
X4066418	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90	TON	205	120		85	
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	781	623		158	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1			
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	1			
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3	EACH	1			1	
Z0002600	BAR SPLICERS	EACH	1476	681		795	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		2		2

PLOT DATE = 12/23/2005
FILE NAME = c:\projects\94964d\03502pa.dgn
PLOT SCALE = 20.0000 / IN.
USER NAME = teasleyck

* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____