

CURB & GUTTER

LOCATION	SIDE	COMB CURB & GUTTER TYPE B-6.24	CONCRETE CURB TYPE B
		FOOT	FOOT
SIMMONS ROAD			
STA 10+52.90 - STA 31+61.85	LT	2105	
STA 10+55.42 - STA 21+16.12	RT	1062	
STA 22+12.37 - STA 31+61.85	RT	950	
STA 31+61.85 - STA 32+38.00	LT		76
STA 31+61.85 - STA 31+95.17	RT		33
MILBURN SCHOOL RD			
STA 14+53.91 - STA 14+87.52	LT	52	
STA 14+54.28 - STA 14+86.50	RT	63	
FAIRWOOD HILLS DR			
STA 3+13.12 - STA 3+59.10	LT	65	
STA 3+12.89 - STA 3+59.10	RT	65	
CHAMPAIGN DRIVE			
STA 9+13.50 - STA 9+60.00	LT	65	
STA 9+12.51 - STA 9+60.00	RT	66	
	TOTAL	4493	109

ENTRANCES

LOCATION	SIDE	WIDTH	DRIVEWAY PAVEMENT REMOVAL	PORTLAND CEMENT CONC DRIVEWAY PAVEMENT, 6 INCH	AGGREGATE BASE COURSE, TYPE B 6 INCH	AGGREGATE BASE COURSE, TYPE B 8 INCH	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	AGGREGATE FOR TEMPORARY ACCESS
			SQ YD	SQ YD	SQ YD	SQ YD	TON	TON
SIMMONS ROAD								
STA 10+02.83 - FAIRWOOD HILLS DR	RT							10
STA 10+07.83 - MILBURN SCHOOL RD	LT							12
STA 11+06.69 - PRIVATE ENTRANCE	LT	20	27	14				4
STA 15+02.31 - PRIVATE ENTRANCE	LT	12		9		24		2
STA 15+86.12 - PRIVATE ENTRANCE	LT	12		9		36		2
STA 19+55.96 - PRIVATE ENTRANCE	LT	12		10		10		8
STA 21+63.40 - CHAMPAIGN DRIVE	RT							2
STA 23+00.00 - FIELD ENTRANCE	LT	20		33				4
STA 25+32.35 - PRIVATE ENTRANCE	LT	12		10		41		2
STA 27+94.01 - PRIVATE ENTRANCE	LT	12	31	10	13		1	2
STA 31+22.00 - PRIVATE ENTRANCE	LT	20		33				4
	TOTAL		58	128	13	111	1	52

NOTE: SEE ENTRANCE DETAIL FOR WIDTH DIMENSION LOCATION

EARTHWORK

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	SHRINKAGE FACTOR	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	%	CU YD	CU YD
SIMMONS ROAD					
STA 9+00.00 - STA 32+40.00	1445	1085	25	1365	-280
MILBURN SCHOOL ROAD					
STA 12+50.00 - STA 14+53.91	75	55	25	90	-35
	TOTAL =	1520		1455	-315

PAVEMENT MARKING

LOCATION	SIDE	POLYUREA PAVEMENT MARKING, TYPE I			DESCRIPTION
		DOUBLE SOLID YELLOW 4"	SOLID WHITE LINE 6"	SOLID WHITE LINE 12"	
		FOOT	FOOT	FOOT	
SIMMONS ROAD					
STA 9+00.70 - STA 9+65.00	☉	129			DOUBLE YELLOW ☉
STA 9+65.00	RT			16	STOP BAR
STA 10+42.00	RT			15	STOP BAR
STA 10+41.50 - STA 31+61.85	☉	4241			DOUBLE YELLOW ☉
MILBURN SCHOOL ROAD					
STA 13+00.00 - STA 14+65.00	☉	330			DOUBLE YELLOW ☉
STA 14+65.00	RT			15	STOP BAR
FAIRWOOD HILLS DRIVE					
STA 3+21.36	LT/RT		61		PEDESTRIAN CROSS WALK
STA 3+27.36	LT/RT		51		PEDESTRIAN CROSS WALK
STA 3+59.11	RT			22	STOP BAR
CHAMPAIGN DRIVE					
STA 9+29.60	RT			20	STOP BAR
STA 9+20.60	LT/RT		55		PEDESTRIAN CROSS WALK
STA 9+26.60	LT/RT		43		PEDESTRIAN CROSS WALK
	TOTAL	4700	210	88	

SIDEWALK

LOCATION	SIDE	SIDEWALK REMOVAL	PORTLAND CEMENT CONC SIDEWALK (4")	DETECTABLE WARNINGS
		SQ FT	SQ FT	SQ FT
SIMMONS ROAD				
STA 10+55.42 - STA 21+16.11	RT		6378	
STA 22+12.37 - STA 33+12.49	RT		6661	
STA 33+12.49 - STA 33+44.91	RT		420	
FAIRWOOD HILLS DRIVE				
STA 3+15.47 - STA 3+59.10	RT	133	346	6
STA 3+15.70 - STA 3+59.11	LT	119	341	6
CHAMPAIGN DRIVE				
STA 9+15.09 - STA 9+60.00	RT	136	348	6
STA 9+16.09 - STA 9+60.00	LT	122	346	6
	TOTAL	510	14840	24

CITY OF O'FALLON, ILLINOIS

SCHEDULE OF QUANTITIES
SHEET 2 OF 4SCALE:
DATE:DRAWN BY:
CHECKED BY: