

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY				
			TOTAL	FC	I	C	DP
72900200	METAL POST - TYPE B	FOOT	125		50		75
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,728		10,728		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	12		12		
78008110	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	5,012	3,600		1412	
78008120	POLYUREA PAVEMENT MARKING - LINE 5"	FOOT	1,106	1,106			
78008180	POLYUREA PAVEMENT MARKING - LINE 24"	FOOT	11			11	
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20			
Z0002000	BAR SPLICERS	EACH	72	72			
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	440	440			
Z0030010	IMPACT ATTENUATORS (TEMPORARY)	EACH	2	2			
XX000830	PIPE UNDERDRAINS, PERFORATED PVC 8 INCH	FOOT	350		350		
XX003967	TURBIDITY CURTAIN	FOOT	2,506	2,506			
XD321156	HIGH VISIBILITY TEMPORARY FENCING	FOOT	1,815	1,815			
XD321561	FURNISHING AND INSTALLING TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL	EACH	1			1	
XD322415	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,050	1,050			
XD712400	TEMPORARY PAVEMENT	SQ YD	228	228			
X3560200	BITUMINOUS BASE COURSE SUPERPAVE 5"	SQ YD	863			863	
X4068414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	99			99	
X4068614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	111			111	
	CONSTRUCTION STAKING	L SUM	1	1			
	PORTLAND CEMENT CONCRETE BIKE TRAIL 6 INCH	SQ FT	44,452		44,452		
	SEEDING, MULCHING, AND FERTILIZING	ACRE	5.6	5.1	0.5		
	LEVEE EMBANKMENT	CU YD	16,372	16,372			
	HANDRAIL 54"	FOOT	2,118		2,118		
	HANDRAIL 24"	FOOT	270	270			
	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	1	1			
	REMOVE, STORE AND REERECT TRAFFIC SIGN	EACH	10	7		3	
	REMOVE, STORE AND REERECT TRAFFIC SIGN WITH LIGHT	EACH	1	1			
	REMOVE, STORE AND REERECT CAMPGROUND ROAD CLOSURE SWING GATE	EACH	1			1	
	BIG BEND LAKE PIPE EXTENSIONS	L SUM	1	1			
	WHEELS PUMP STATION STRUCTURE	L SUM	1	1			
	WHEELS PUMP STATION ELECTRICAL WORK	L SUM	1	1			
	WHEELS PUMP STATION PUMPS, PUMP CONTROLS, PIPING AND APPURTANCES	LSUM	1	1			
	MINER STREET PUMP STATION STRUCTURE	L SUM	1	1			
	ELECTRIC SERVICE CONNECTION - MINER STREET PUMP STATION	L SUM	1	1			
	ELECTRIC SERVICE INSTALLATION - MINER STREET PUMP STATION	L SUM	1	1			
	MINER STREET PUMP STATION ELECTRICAL WORK	L SUM	1	1			
	MINER STREET PUMP STATION PUMPS, PUMP CONTROLS, PIPING AND APPURTANCES	LSUM	1	1			
	RAND ROAD FLOOD GATE	L SUM	1	1			
	BALLARD ROAD FLOOD GATE	L SUM	1	1			
	TIDFLEX FOR 6" DUCTILE IRON PIPE	EACH	1	1			
	TIDFLEX FOR 12" REINFORCED CONCRETE PIPE	EACH	3	3			
	TIDFLEX FOR 15" REINFORCED CONCRETE PIPE	EACH	2	2			
	TIDFLEX FOR 24" REINFORCED CONCRETE PIPE	EACH	2	2			
	TIDFLEX FOR 36" REINFORCED CONCRETE PIPE	EACH	1	1			
	TIDFLEX FOR 96" REINFORCED CONCRETE PIPE	EACH	1	1			
	MICROPILE	EACH	8	8			
	MICROPILE, TENSION TEST PILE	EACH	1	1			

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY				
			TOTAL	FC	I	C	DP
	ARCHITECTURAL CONCRETE FORM LINER FINISH	SQ FT	24,602	23,998			604
	MINER STREET GATE STRUCTURE	L SUM	1	1			
	ELECTRIC SERVICE CONNECTION - BIKE TRAIL LIGHTING SYSTEM	L SUM	1	1			
	ELECTRIC SERVICE INSTALLATION - BIKE TRAIL LIGHTING SYSTEM	L SUM	1	1			
	BIKE TRAIL LIGHTING SYSTEM - FLOOD CONTROL	L SUM	1	1			
	BIKE TRAIL LIGHTING SYSTEM - DES PLAINES	L SUM	1				1
	MINER STREET WATER MAIN RELOCATION	L SUM	1				1
	INTERCEPTOR NO. 9 STRUCTURE	L SUM	1	1			
	TEMPORARY CURB AND GUTTER	FOOT	20	20			
	1842 E. MINER STREET DEMOLITION AND MODIFICATIONS	L SUM	1				1
	1844 E. MINER STREET DEMOLITION AND MODIFICATIONS	L SUM	1				1
	MINER ST. STAIRS	L SUM	1				1

QUANTITY LEGEND

- TOTAL - TOTAL PROJECT QUANTITY
- FC - IDNR FLOOD CONTROL QUANTITY
- I - IDNR TRAILS QUANTITY
- C - CAMPGROUND ROAD QUANTITY
- DP - CITY OF DES PLAINES QUANTITY

DESIGNED BY: _____
DRAWN BY: _____
CHECKED BY: _____
CHECKED BY: _____

01/30/2006 04:10:50 PM P:\NP60003332\General\Shit\02g04.sht