

DESIGNED BY: D.E.S.
DRAWN BY: H.A.R.
CHECKED BY: _____
CHECKED BY: _____

3-1/2" #2-2/2" RGS CONDUIT IN TRENCH
3-1/2" #2-2/2" RGS CONDUIT IN TRENCH

3-1/2" #2-2/2" RGS CONDUIT IN TRENCH, PUSHED UNDER PAVEMENT
3-1/2" #2-2/2" RGS CONDUIT IN TRENCH, PUSHED UNDER PAVEMENT

MINER STREET
PUMP STATION
CONTROL PANEL

INSTALL MANUFACTURES
CABLE IN 2-2" RGS CONDUIT
IN TRENCH


3-1/2" #2-2/2" RGS CONDUIT IN TRENCH

NOTES:

- SEE SHEET NUMBER E-1 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
- 12" x 8" x 8" PULLBOX EMBEDDED IN FLOODWALL ABOVE SHEET PILE.
- 1-1/2" RGS CONDUIT EMBEDDED IN FLOODWALL. INSTALL CONDUIT FOR MOUNTING FLOOD WALL LUMINAIRE 9'-5" ABOVE THE BIKE TRAIL PAVEMENT. SEE DETAIL ON SHEET E-2.

CABLE GROUPINGS SCHEDULE

- (A) 6-1/2" #6 & 1-1/2" #8 GROUND IN 2" PVC CONDUIT EMBEDDED IN FLOOD WALL
- (B) 3-1/2" #2, 3-1/2" #6 & 1-1/2" #2 GROUND IN 2" PVC CONDUIT EMBEDDED IN FLOOD WALL
- (D) 3-1/2" #2, 3-1/2" #6 & 1-1/2" #2 GROUND IN 2" RGS CONDUIT AND 6-1/2" #6 & 1-1/2" #8 GROUND IN 2" RGS CONDUIT IN COMMON TRENCH.



REVISION	
DATE	DESCRIPTION

PLANS PREPARED BY:
CTE | AECOM

CTE
303 East Wacker Drive, Suite 600, Chicago, Illinois 60601-5276
T 312.938.0300 F 312.938.1109 www.cte.aecom.com

FR-416

01/30/2005 07:40:03 PM p:\p60003332\elect\shh\06E-05.sht