SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR107812	L-807 WIND CONE-12' INTERNALLY LIT	EA	1	
AR107900	REMOVE WIND CONE	EA	1	
AR108158	1/C #8 5KV UG CABLE IN UD	LF	12,614	
AR108554	2/C #4 600V UG CABLE IN UD	LF	920	
AR108656	3/C #6 600V UG CABLE IN UD	LF	870	
AR108800	CONTROL CABLE	LF	560	
AR109100	CONSTRUCT ELECTRICAL VAULT	LS	1	
AR109200	INSTALL ELECTRICAL EQUIPMENT	LS	1	
AR109901	REMOVE ELECTRICAL VAULT	LS	1	
AR110014	4" DIRECTIONAL BORE	LF	390	
AR110503	3-WAY CONCRETE ENCASED DUCT	LF	216	
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	66	
AR110610	ELECTRICAL HANDHOLE	EA	3	
AR125410	MITL-STAKE MOUNTED	EA	42	
AR125415	MITL-BASE MOUNTED	EA	8	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EA	1	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EA	2	
AR125901	REMOVE STAKE MOUNTED LIGHT	EA	42	
AR125902	REMOVE BASE MOUNTED LIGHT	EA	8	
AR125904	REMOVE TAXI GUIDANCE SIGN	EA	3	
AR125989	REFURBISH PLASI	EA	1	
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR150540	HAUL ROUTE	LS	1	
AR156510	SILT FENCE	LF	100	
AR156511	DITCH CHECK	EA	2	
AR156512	BALES	EA	16	
AR156520	INLET PROTECTION	EA	3	
AR201660	BITUMINOUS CRACK REPAIR	LF	2812	
AR401610	BITUMINOUS SURFACE COURSE	TON	1246	
AR401620	BIT. SURFACE COURSE, LEVELING	TON	800	
AR401655	BUTT JOINT CONSTRUCTION	SY	1778	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	489	
AR402622	POROUS FRICTION COURSE, 0.10'	SY	10,389	
AR501900	REMOVE PCC PAVEMENT	SY	29	
AR510510	TIE DOWN	EA	16	
AR510900	REMOVE TIE DOWN	EA	24	
AR603510	BITUMINOUS TACK COAT	GAL	4848	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	3820	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	588	
AR705410	POROUS BACKFILL	CY	224	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	LF	1339	
AR705630	UNDERDRAIN INSPECTION HOLE	EA	5	
AR751909	REMOVE INSPECTION HOLE	EA	3	
AR751949	ADJUST INSPECTION HOLE	EA	9	
AR800590	4/C #6 600V UG CABLE IN UD	LF	310	
AR800591	UPGRADE AIRPORT ROTATING BEACON	LS	1	
AR901510	SEEDING	AC	1.4	
AR905520	TOPSOILING (FROM OFF SITE)	CY	440	
AR908510	MULCHING	AC	1.4	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES, INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED PAVEMENT PREPARATION PLAN STA. 4+00 TO STA. 12+00
5	PROPOSED PAVEMENT PREPARATION PLAN STA. 12+00 TO STA. 20+00
6	PROPOSED PAVEMENT PREPARATION PLAN STA. 20+00 TO STA. 26+00
7	PROPOSED TYPICAL SECTIONS
8	PROPOSED PLAN AND PROFILE TAXIWAY B STA. 7+00 TO STA. 21+00
9	PROPOSED PLAN AND PROFILE TAXIWAY B STA. 21+00 TO STA. 24+81.11
10	PROPOSED PLAN AND PROFILE TAXIWAY C STA. 100+00 TO STA. 102+96.21
11	PROPOSED STAKING PLAN STA. 4+00 TO STA. 12+00
12	PROPOSED STAKING PLAN STA. 12+00 TO STA. 20+00
13	PROPOSED STAKING PLAN STA. 20+00 TO STA. 26+00
14	PROPOSED DRAINAGE PLAN
15	UNDERDRAIN NOTES AND DETAILS
16	PROPOSED STORMWATER POLLUTION PREVENTION PLAN
17	EXISTING TIE DOWN REMOVAL AND MARKING PLAN
18	PROPOSED MARKING PLAN STA 4+00 TO STA. 12+00
19	PROPOSED MARKING PLAN STA. 12+00 TO STA. 20+00
20	PROPOSED MARKING PLAN STA. 20+00 TO STA. 26+00
21	EXISTING ELECTRICAL PLAN STA. 4+00 TO STA. 12+00
22	EXISTING ELECTRICAL PLAN STA. 12+00 TO STA. 20+00
23	EXISTING ELECTRICAL PLAN STA. 20+00 TO STA. 26+00
24	PROPOSED ELECTRICAL PLAN STA. 4+00 TO STA. 12+00
25	PROPOSED ELECTRICAL PLAN TAXIWAY "A"
26	PROPOSED ELECTRICAL PLAN STA. 12+00 TO STA. 20+00
27	PROPOSED ELECTRICAL PLAN STA. 20+00 TO STA. 26+00
28	WIND CONE ELEVATION DETAIL
29	PROPOSED PLASI WIRING DETAILS & NOTES
30	LIGHTNING PROTECTION DETAILS FOR BEACON
31	ELECTRICAL DETAILS
32	ELECTRICAL DETAILS
33	ELECTRICAL NOTES
34	ELECTRICAL NOTES
35	ELECTRICAL LEGEND AND ABBREVEATIONS
36	EXISTING VAULT SITE PLAN
37	EXISTING VAULT ELECTRICAL ONE-LINE DIAGRAM
38	PROPOSED VAULT SITE PLAN
39	PROPOSED AIRPORT ELECTRICAL VAULT EQUIPMENT PLAN
40	VAULT LIGHTING AND RECEPTACLE PLAN
41	PROPOSED AIRPORT ELECTRICAL VAULT WALL ELEVATIONS
42	PROPOSED VAULT ELECTRICAL ONE-LINE DIAGRAM SHEET 1
43	PROPOSED VAULT ELECTRICAL ONE-LINE DIAGRAM SHEET 2
44	PANEL SCHEDULES & DETAILS
45	HIGH VOLTAGE WIRING SCHEMATIC
46	AIRFIELD LIGHTING CONTROL SCHEMATIC
47	AIRFIELD LIGHTING CONTROL SCHEMATIC CONTINUED
48	LIGHTING CONTACTOR PANEL DETAIL
49	LEGEND PLATE SCHEDULE AND TRANSFORMER WIRING DIAGRAMS
50	ELECTRICAL AND GROUNDING DETAILS
51	PROPOSED APRON CROSS-SECTIONS STA. 7+02.28 TO STA. 7+18.12
52	PROPOSED APRON CROSS-SECTIONS STA. 7+50 TO STA. 8+00
53	PROPOSED APRON CROSS-SECTIONS STA. 8+50 TO STA. 9+00
54	PROPOSED APRON CROSS-SECTIONS STA. 9+29.35 TO STA. 9+64.87
55	PROPOSED APRON CROSS-SECTIONS STA. 9+79.35 TO STA. 10+19.35
56	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 10+21.20 TO STA. 10+71.20
57	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 11+00 TO STA. 12+50
58	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 12+97.64 TO STA. 13+47.72
59	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 14+22.72 TO STA. 15+00
60	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 15+50 TO STA. 17+00
61	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 17+50 TO STA. 18+50
62	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 19+00 TO STA. 20+50
63	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 21+00 TO STA. 22+50
64	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 23+00 TO STA. 24+22.63
65	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 24+50 TO STA. 24+81.11
66	PROPOSED TAXIWAY "C" CROSS-SECTIONS STA. 100+30 TO STA. 101+00
67	PROPOSED TAXIWAY "C" CROSS-SECTIONS STA. 101+50 TO STA. 102+96.21

DATE	REVISION	BY

KEWANEE MUNICIPAL AIRPORT
KEWANEE, HENRY COUNTY, ILLINOIS

IL. PROJ.: EZI-3533 A.I.P. PROJ.: 3-17-0058-B10

HS Project No. 810-06TXYD.0800
Filename R-002FLP.DWG
Scale NOT TO SCALE
Date 08/01/05

LAYOUT	R.A.W.	08/01/05
DRAWN	B.A.K.	08/01/05
REVIEWED	C.A.H.	XX/XX/XX

HANSON

Hanson Professional Services Inc.
3121 Coventry Trail, Suite 100
Indianapolis, Indiana 46214
Offices Nationwide

OVERLAY TXY & APRON CONSTRUCT VAULT

SUMMARY OF QUANTITIES, INDEX TO SHEETS

2

JAN 18, 2006 7:51 PM RAW
I:\AIRPORTS\KEWANEE\810-06TXYD\AIRPORT\SHEETS\R-002FLP.DWG - Model