

DATE	REVISION	BY

SUMMARY OF QUANTITIES


ITEM NO.	DESCRIPTION	UNIT	TOTAL		AS BUILT		TOTAL		AS BUILT	
			FEDERAL/LOCAL QUANTITIES	FEDERAL/LOCAL QUANTITIES	FED/STATE/LOCAL QUANTITIES	FED/STATE/LOCAL QUANTITIES	PROJECT QUANTITIES	PROJECT QUANTITIES		
AR108965	RELOCATE CABLE	L.S.			1		1		1	
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH			4		4		4	
AR150510	ENGINEER'S FIELD OFFICE	L.S.			1		1		1	
AR150540	HAUL ROUTE	L.S.			1		1		1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.			1,997		1,997		1,997	
AR156511	DITCH CHECK	EACH			3		3		3	
AR156513	SEPARATION FABRIC	S.Y.	690		4,153		4,843		4,843	
AR156521	HEADWALL PROTECTION	EACH			3		3		3	
AR201610	BITUMINOUS BASE COURSE	TON	102		613		715		715	
AR208540	OVERSIZED AGGREGATE	TON	319		1,919		2,238		2,238	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	278		1,674		1,952		1,952	
AR401610	BITUMINOUS SURFACE COURSE	TON	61		365		426		426	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.			270		270		270	
AR602510	BITUMINOUS PRIME COAT	GAL.	240		1,442		1,682		1,682	
AR603510	BITUMINOUS TACK COAT	GAL.	102		613		715		715	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.			817		817		817	
AR701515	15" RCP, CLASS IV	L.F.			63		63		63	
AR751940	ADJUST INLET	EACH			2		2		2	
AR752615	CONCRETE HEADWALL 15"	EACH			1		1		1	
AR752903	REMOVE HEADWALL	EACH			1		1		1	
AR901510	SEEDING	ACRE			1.8		1.8		1.8	
AR908510	MULCHING	ACRE			1.8		1.8		1.8	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED STORMWATER POLLUTION PREVENTION PLAN
5	PROPOSED EROSION CONTROL DETAILS
6	PROPOSED CONSTRUCTION PLAN
7	PROPOSED PARTICIPATION PLAN
8	PROPOSED DRAINAGE PLAN
9	PROPOSED PIPE PLAN AND PROFILE
10	PROPOSED STAKING PLAN
11	PROPOSED MARKING PLAN
12	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 348+50 TO STA. 348+75
13	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 349+00 TO STA. 349+25
14	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 349+44.59 TO STA. 349+50
15	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 349+59.59 TO STA. 349+69.59
16	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 349+75 TO STA. 350+00
17	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 350+24.09 TO STA. 350+75.09
18	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 351+00 TO STA. 351+34.97
19	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 351+50 TO STA. 352+00
20	PROPOSED CROSS-SECTIONS FOR ACCESS TAXIWAY STA. 352+00 TO STA. 352+75

MARSHALL COUNTY AIRPORT
LACON, ILLINOIS

Project No.	811-06THCD-0800
Revision	R-002FLP.DWG
Scale	N/A
Date	10/10/05
LAYOUT	B.A.K. 10/10/05
DRAWN	B.A.K. 10/10/05
REVIEWED	C.A.H. xx/xx/xx



PROPOSED T-HANGAR
ACCESS TAXIWAY
SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS