

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITIES	
			AS AWARDED	AS BUILT
AR108158	1/C #8 5KV UG CABLE IN UD	LF.	670	
AR108258	2/C #8 5KV UG CABLE IN UD	LF.	80	
AR125415	MIL - BASE MOUNTED	EACH	5	
AR125931	REPLACE LIGHT LENSE	EACH	4	
AR125944	ADJUST TAXI GUIDANCE SIGN	EACH	1	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	6	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EACH	1	
AR150512	ENGINEERS FIELD OFFICE (MONTHLY)	C.M.	8	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR151450	CLEARING AND GRUBBING	ACRE	2.1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	48,330	
AR152440	BORROW EXCAVATION	C.Y.	14,165	
AR156500	TEMPORARY EROSION CONTROL	L.S.	1	
AR209511	CRUSHED AGGREGATE BASE, (CA1)	TON	100	
AR620510	PAVEMENT MARKING	S.F.	4,350	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	12,100	
AR801604	SETTLEMENT PLATES	EACH	8	
AR801605	REPLACE TAXI GUIDANCE SIGN PANEL	EACH	7	
AR801614	SUPPLY TAXI GUIDANCE SIGN PANEL	EACH	20	
AR901510	SEEDING	ACRE	21	
AR908513	MULCHING - METHOD 3	ACRE	21	

GENERAL NOTES:

1. THE CONTRACTOR SHALL SALVAGE EXISTING AIRFIELD LIGHTING EQUIPMENT AS DETAILED IN THE CONSTRUCTION PLANS AND SPECIAL PROVISIONS PRIOR TO THE START OF EARTHWORK AND/OR PAVING ACTIVITIES. SALVAGED EQUIPMENT SHALL BE CLEANED AND REUSED OR DELIVERED TO THE METROPOLITAN AIRPORT AUTHORITY.
2. CROSS SECTION SLOPES, CENTERLINE PROFILE GRADES, AND ALL SPOT GRADES SHALL BE SUBJECT TO CHANGE, AS APPROVED BY THE RESIDENT ENGINEER, AT THE TIME OF CONSTRUCTION.
3. THE CONTRACTOR SHALL EXCAVATE TEMPORARY EROSION CONTROL DRAINAGE SWALES, AS REQUIRED BY THE ENGINEER, TO CONTROL STORM WATER RUN-OFF.
4. THE CONTRACT 152 - EARTHWORK ITEMS SHALL INCLUDE ALL COSTS ASSOCIATED WITH EXCAVATION OF SOILS, HAULING OF SOILS, STOCKPILING SOILS, INSTALLATION OF SOILS, COMPACTION OF SOILS, GRADING OF SOILS, INSTALLATION AND REMOVAL OF HAUL ROADS OR ROUTES, RESTORATION OF HAUL ROADS OR ROUTES, DISPOSAL OF WASTE SOILS, CLEANING OF PAVEMENTS, AND ALL OTHER ITEMS THAT ARE REQUIRED TO COMPLETE THE EARTHWORK. THESE ITEMS SHALL BE PAID FOR BASED UPON THE CUBIC YARDS OF MATERIALS REMOVED AND/OR REQUIRED AS ACCEPTED BY THE ENGINEER. SEE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.
5. AFTER CONSTRUCTION HAS BEEN COMPLETED, THE CONTRACTOR SHALL SEED AND HYDRAULIC MULCH ALL DISTURBED AREAS PER SPECIAL PROVISIONS 901 AND 908. ONLY SEEDING AND MULCHING AREAS WITHIN THE LIMITS OF CONSTRUCTION/SEEDING WILL BE ELIGIBLE FOR PAYMENT UNDER THESE CONTRACT PAY ITEMS. AREAS OUTSIDE OF THE LIMITS OF CONSTRUCTION/SEEDING SHALL BE SEEDED AND MULCHED BY THE CONTRACTOR PER SPECIAL PROVISION 901/908, BUT SHALL NOT BE MEASURED FOR PAYMENT.
6. ITEM AR908513 MULCHING - METHOD 3 SHALL BE ACCOMPLISHED FOLLOWING THE METHODS AND PROCEDURES OUTLINED IN THE IDOT-DOA SUPPLEMENTAL SPECIFICATIONS AND IN THE ILLINOIS DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION SECTION 251, METHOD 3 (HYDRAULIC MULCH).