



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 24, 2023

SUBJECT: FAP Route 301 (US 20)
Project NHPP-25G6(672)
Section (3,4)RS-2
Winnebago County
Contract No. 64M40
Item No. 32, March 10, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page 1 of the Special Provisions.
3. Revised sheets 2 and 8 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the “Standard Specifications for Road and Bridge Construction, adopted January 1, 2022”, the latest edition of the “Manual on Uniform Traffic Control Devices for Streets and Highways”, and the “Manual of Test Procedures for Materials” in effect on the date of invitation for bids, and the “Supplemental Specifications and Recurring Special Provisions” indicated on the Check Sheet included herein, which apply to and govern the construction of FAP Route 301 (US 20), Project NHPP-25G6(672), Section (3,4)RS-2, Winnebago County, Contract No. #64M40 and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION OF PROJECT

US 20 from the Rock River to 0.7 mile west of Alpine Road.

DESCRIPTION OF PROJECT

Cold milling and hot-mix asphalt resurfacing on US 20 from the Rock River to 0.7 mile west of Alpine Road in Rockford. Scope includes guardrail improvements, ramp resurfacing, and US 20/IL 251 lighting updates.

TRAFFIC CONTROL PLAN

Effective: January 14, 1999

Revised: January 13, 2017

Standards:

701006	701101	701106	701301	701400	701401
701406	701411	701416			701426
7001427	701428	701451	701456	701901	704001

Details:

District Standard 34.1
District Standard 41.1

Signs:

“BUMP” (W8-1(O)48) signs shall be installed as directed by the Engineer.

When covering existing Department signs, no tape shall be used on the reflective portion of the sign. Contact the District sign shop for covering techniques. Revised February 24, 2023