



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 23, 2023

SUBJECT OR 2626 (Old Arlington Heights Road)
Section OR 2626 22 RESURFACE
Cook County
Contract No. 62R70
Item No. 111, March 10, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added page 69 to the Special Provisions
4. Revised sheets 1, 2, 7 & 12 of the Plans
5. Added sheets 12A & 12B to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

SUBMISSION OF PAYROLL RECORDS (BDE) 58
SURFACE TESTING OF PAVEMENTS – IRI (BDE) 60
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 66
WEEKLY DBE TRUCKING REPORTS (BDE)..... 66
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 67
WORKING DAYS (BDE) 68
DRILL AND GROUT BARS 69

Revised 2/23/2023

DRILL AND GROUT BARS

Description. This work shall consist of furnishing, drilling and epoxy grouting reinforcement bars at the locations shown on the plans or as directed by the Engineer. Epoxy grout materials shall be according to Article 584.02 of the Standard Specifications. Drill and Grout Bars shall be performed according to Article 584.03 of the Standard Specifications.

Method of Measurement. Drill and Grout Bars will be measured for payment in place and quantity computed per each.

Basis of Payment. This work will be paid for at the contract unit price per each for DRILL AND GROUT BARS. The unit price shall include all equipment, labor and materials required to install the bars into the existing concrete.

Added 2/23/2023