

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	9
STA.	TO STA.		60997	
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	BRIDGE 80% FED 20% STATE X631-5B	RETAINING WALL 80% FED 20% STATE Y007	LIGHTING 100% VILLAGE Y030-1E	TRAFFIC SIGNALS TL 22 @ MALL DR. 100% VILL. Y031-1F	TRAFFIC SIGNALS TL 22 @ US 12 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ ELA 80% FED 10% STATE 5% VILL. 5% COUNTY Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. Y031-1F	TRAFFIC SIGNAL EVP EQUIPMENT 100% VILL. Y031-3D	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. SFTY-1B	WATER MAIN/SAN. SEWER 80% FED 20% STATE Y060	WATER MAIN/SAN. SEWER 100% VILL. Y060	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL J000-1A	100% VILLAGE OF LAKE ZURICH Y031-1F
60500040	REMOVING MANHOLES	EACH	31	22																	
60500050	REMOVING CATCH BASINS	EACH	43	43																	
60500060	REMOVING INLETS	EACH	35	35																	
60500105	FILLING MANHOLES	EACH	13	2														5	6		
60500205	FILLING CATCH BASINS	EACH	3	3																	
60500405	FILLING VALVE VAULTS	EACH	17																	17	
M6060010	CLASS SI CONCRETE (OUTLET)	CU M	8	8																	
M6060070	CONCRETE CURB, TYPE B	METER	510	511																5	
M6060260	CONCRETE GUTTER, TYPE A	METER	153	153																	
M6060400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.15	METER	58	58																	
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	1111	1111																	
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	12,441	12,366																	75
M6061930	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-10.30	METER	90	90																	
M6061990	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-10.60	METER	90	90																	
M6063600	CONCRETE MEDIAN SURFACE, 100MM	SQ M	788	788																	
M6064200	CONCRETE MEDIAN, TYPE SB-15.60	SQ M	2043	1948																	95
M6066000	CORRUGATED MEDIAN	SQ M	206	206																	
M6066020	CORRUGATED MEDIAN, MODIFIED	SQ M	99	99																	
* M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	53.34	53.34																	
* 63100045	TRAFFIC BARRIER TERMINAL TYPE 2	EACH	1	1																	
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	1																	
* M6320030	GUARDRAIL REMOVAL	METER	472	472																	
* 66900500	BETX SOIL ANALYSIS	EACH	3	3																	
* 66900610	ARSENIC AND PH SOIL ANALYSIS	EACH	2	2																	
* 66900635	LEAD TCLP SOIL ANALYSIS	EACH	2	2																	
* 66900640	VOCS AND SVOCS SOIL ANALYSIS	EACH	4	4																	
* M6690200	NON-SPECIAL WASTE DISPOSAL	CU M	1268	1268																	

* SPECIALTY ITEMS
VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
SUMMARY OF QUANTITIES #7

SCALE : NA
DATE : 09/21/04

DESIGNED BY KLM
CHECKED BY DDL

Rev.