

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	10
STA.		TO STA.		60997
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE	BRIDGE 80% FED 20% STATE	RETAINING WALL 80% FED 20% STATE	LIGHTING 100% VILLAGE	TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL.	TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE	TRAFFIC SIGNALS IL 22 @ ELA 80% FED 10% STATE 5% VILL 5% COUNTY	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL.	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL.	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL.	TRAFFIC SIGNAL EQUIPMENT 100% VILL.	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL.	WATER MAIN/SAN. SEWER 80% FED 20% STATE	WATER MAIN/SAN. SEWER 100% VILL.	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL	100% VILLAGE OF LAKE ZURICH	
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	20	20																		
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	20	20																		
67100100	MOBILIZATION	L SUM	1	1																		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1																		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	200	200																		
M7030100	SHORT-TERM PAVEMENT MARKING	METER	1283	1283																		
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	167.7	167.7																		
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	41268	41268																		
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150 MM	METER	1031	1031																		
M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	106	106																		
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	678	678																		
M7030510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ M	130.4	130.4																		
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	60,218	60,218																		
M7030540	PAVEMENT MARKING TAPE, TYPE III 150MM	METER	3833	3833																		
M7030560	PAVEMENT MARKING TAPE, TYPE III 300MM	METER	20	20																		
M7030580	PAVEMENT MARKING TAPE, TYPE III 600MM	METER	698	698																		
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	11,098	11,098																		
M7040100	TEMPORARY CONCRETE BARRIER	METER	339	339																		
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	353	353																		
M7200100	SIGN PANEL - TYPE 1	SQ M	86.01	71.52					1.53	4.04	2.09	3.21	2.09	1.53								
M7200200	SIGN PANEL - TYPE 2	SQ M	4.64						2.32					2.32								
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	79	79																		
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	13	13																		
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	23	23																		
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4																		
M7240310	REMOVE SIGN PANEL - TYPE 1	SQ M	3.52	3.52																		
M7240320	REMOVE SIGN PANEL - TYPE 2	SQ M	3.20	3.20																		

*SPECIALTY ITEMS
VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
SUMMARY OF QUANTITIES #8

SCALE : NA
DATE : 08/21/04

DESIGNED BY KLM
CHECKED BY DDL

Rev.