

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	12
STA.	TO STA.		60997	
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	BRIDGE 80% FED 20% STATE X77-1-5B	RETAINING WALL 80% FED 20% STATE Y007	LIGHTING 100% VILLAGE Y030-1E	TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ ELA 80% FED 10% STATE 5% VILL. 3% COUNTY Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. Y031-1F	TRAFFIC SIGNAL EVP EQUIPMENT 100% VILL. Y031-3D	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. SFTY-1B	WATER MAIN/ SAN. SEWER 80% FED 20% STATE Y060	WATER MAIN/ SAN. SEWER 100% VILL. Y060	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL J000-1A	100% VILLAGE OF LAKE ZURICH Y031-1F	
M8100080	CONDUIT IN TRENCH, 75MM DIA., GALVANIZED	METER	17							8			9									
M8100100	CONDUIT IN TRENCH, 100MM DIA., GALVANIZED STEEL	METER	130					8	13	29	11	25	22	22								
M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	582				107	36	88	16		91	35				209					
M8101060	CONDUIT PUSHED, 65MM DIA., GALVANIZED STEEL	METER	20						20													
M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	584					77	119	101	59	86	52	90								
81400100	HANDHOLE	EACH	54					6	8	6	4	8	6	5								11
81400200	HEAVY-DUTY HANDHOLE	EACH	23					4	4	3	2	4	2	4								
81400300	DOUBLE HANDHOLE	EACH	7					1	1	1	1	1	1	1								
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	4368				266	194	329	275	237	338	200	190								2339
M8160210	UNIT DUCT, 2"X10XLP, 1"X10 XLP GROUND 20MM POLYETHYLENE	METER	385																			
M8170805	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 2	METER	18					18														
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	9					9														
82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240VOLT	EACH	1					1														
M8303110	LIGHT POLE, STEEL, 12.0M M.H., 1.8M MAST ARM	EACH	5					5														
M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	15					15														
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4							1	1	1		1								
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1								1	1	1	1								
85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1																			
86000100	MASTER CONTROLLER	EACH	1							1												
86400100	TRANSCEIVER - FIBER OPTIC	EACH	7					1	1	1	1	1	1	1								
M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	METER	1353					165	105	217	190	263	212	201								
M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	3529					407	426	582	418	706	480	510								
M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	2564					220	826	264	317	307	353	277								
M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	3211					421	670	522	205	628	224	541								
M8731300	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	METER	3712					467	791	575	308	688	343	540								
M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	179					42	25	31	40	12	13	16								

VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 22  
FROM US RTE 12 TO BUESCHING RD  
SUMMARY OF QUANTITIES #10

SCALE : NA  
DATE : 08/21/04  
DESIGNED BY KLM  
CHECKED BY DDL

Rev.