

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	15
STA.		TO STA.		60997
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	PAY ITEM	UNIT	LABOR TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	BRIDGE 80% FED 20% STATE X771-5B	RETAINING WALL 80% FED 20% STATE Y007	LIGHTING 100% VILLAGE Y030-1E	TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ ELA 80% FED 10% STATE 5% VILL 5% COUNTY Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. Y031-1F	TRAFFIC SIGNAL EQUIPMENT 100% VILL. Y031-3D	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. SFTY-1B	WATER MAIN/ SAN. SEWER 80% FED 20% STATE Y060	WATER MAIN/ SAN. SEWER 100% VILL. Y060	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL J000-1A	100% VILLAGE OF LAKE ZURICH Y031-1F
MX033089	ENGINEERED FILL, CLASS 2	CU M	8753	8753																	
MX033109	DRILLING AND SETTING SOLDIER PILES	CU M	622.5		98.5	524															
MX355150	BITUMINOUS BASE COURSE SUPERPAVE, 150MM	SQ M	970	970																	
MX355200	BITUMINOUS BASE COURSE SUPERPAVE, 200MM	SQ M	3524	3524																	
MX356370	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 200MM	SQ M	89	89																	
MX406022	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	M TON	825	521													304				
MX406076	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	M TON	1910	1910																	
MX406012	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	M TON	834	834																	
MX406214	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	M TON	1387	1387																	
MX406218	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	M TON	1223	1223																	
MX482280	BITUMINOUS SHOULDERS SUPERPAVE 150MM	SQ M	66	66																	
MX482330	BITUMINOUS SHOULDERS SUPERPAVE 200MM	SQ M	2410	2410																	
MX500510	FLOATING BEARINGS, NON-GUIDED EXPANSION, 750KN	EACH	2		2																
MX602400	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	10	10																	
MX606050	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-5.60	METER	290	290																	
* MX871055	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	METER	4091														4091				
* MX873027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO.6 1C	METER	1273				174	238	179	177	184	153	168								
* MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	1279												1279						
* MX878030	CONCRETE FOUNDATION, TYPE E 900 MM DIAMETER	METER	69.0					9.2	13.8	4.6	18.4	4.6	18.4								
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	96,983	96,377																	606
MZ013825	CONTROLLED LOW STRENGTH MATERIAL	CU M	70																		70
* MZ015000	CURB STOPS 25MM	EACH	16																		16
* MZ015200	CURB STOPS 35MM	EACH	2																		2
* MZ015300	CURB STOPS 50MM	EACH	2																		2
MZ022800	FENCE REMOVAL	METER	585	585																	
* MZ056800	SANITARY SEWER 150MM	METER	50																		50

* SPECIALTY ITEMS
VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
SUMMARY OF QUANTITIES #13

SCALE : NA
DATE : 05/21/04

DESIGNED BY KLM
CHECKED BY DDL

Rev.