

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	16
STA.		TO STA.		60997
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	BRIDGE 80% FED 20% STATE X771-5B	RETAINING WALL 80% FED 20% STATE Y007	LIGHTING 100% VILLAGE Y030-1E	TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ ELA 80% FED 10% STATE 5% VILL. 5% COUNTY Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. Y031-1F	TRAFFIC SIGNAL EVP EQUIPMENT 100% VILL. Y031-3D	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. SFTY-1B	WATER MAIN/ SAN. SEWER 80% FED 20% STATE Y060	WATER MAIN/ SAN. SEWER 100% VILL. Y060	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL J000-1A	100% VILLAGE OF LAKE ZURICH Y031-1F
* MZ056900	SANITARY SEWER 200MM	METER	246															170	76		
* MZ057000	SANITARY SEWER 250MM	METER	157																	157	
* MZ057100	SANITARY SEWER 300MM	METER	471																	471	
* MZ067600	STEEL CASINGS 450MM	METER	37																	37	
* MZ067700	STEEL CASINGS 500MM	METER	22																	22	
MX030493	SUBBALLAST (CRUSHED STONE)	M TON	1037	1037																	
* X0321556	SANTARY MANHOLES TO BE ADJUSTED	EACH	17															2	15		
X0321809	PERMANENT GROUND ANCHOR	EACH	20		8	12															
X0322938	TEMPORARY END SECTION	EACH	1	1																	
X0322996	END SECTIONS TO BE RELOCATED	EACH	1	1																	
X0323092	HEADWALL REMOVAL	EACH	2	2																	
X0323236	TEMPORARY INLET	EACH	14	14																	
* X0323793	PAINT NEW MAST ARM AND POLE, UNDER 12.19 M	EACH	4																		4
* X0323794	PAINT NEW MAST ARM AND POLE, 12.19 M AND OVER	EACH	6																		6
* X0323797	PAINT NEW TRAFFIC SIGNAL POST	EACH	5																		5
X0976500	END SECTIONS TO BE REMOVED	EACH	11	11																	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	23	23																	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	53	53																	
X4023000	TEMPORARY ACCESS (ROAD)	EACH	16	16																	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	72	72																	
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	7					1	1	1	1	1	1	1	1						
* X8800020	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	28					4	6	3	4	3	4	4	4						
* X8800035	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5						1		2		2								
* X8800038	SIGNAL HEAD, L.E.D., 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2							2											
* X8800040	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION BRACKET MOUNTED	EACH	19					4	1	2	2	4	2	4							
* X8800045	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION MAST ARM MOUNTED	EACH	28					4	8	3	2	5	2	4							
* X8800060	SIGNAL HEAD, L.E.D., 2-FACE, 3-SECTION BRACKET MOUNTED	EACH	1						1												

* SPECIALTY ITEMS
VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
SUMMARY OF QUANTITIES #14

SCALE : NA
DATE : 03/21/04

DESIGNED BY KLM
CHECKED BY DDL

Rev.