

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	41
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

## DRIVEWAY SCHEDULE

60997

LOCATION	DRIVEWAY PAVEMENT REMOVAL (S.M.)	CURB REMOVAL (METER)	CURB & GUTTER REMOVAL (METER)	P.C.C. MEDIAN REMOVAL (S.M.)	DRIVEWAY WIDTH E/P -E/P (METER)	BITUMINOUS BASE COURSE SUPERPAVE 150mm (S.M.)	BITUMINOUS BASE COURSE SUPERPAVE 200mm (S.M.)	BIT. CONC. SURF. CSE., SUPERPAVE MIX. "C", N50 50mm (M TON)	TYPE B CURB (METER)	CURB & GUTTER TYPE B-15.30 (METER)	CURB & GUTTER TYPE B-15.15 (METER)	P.C.C. MEDIAN (S.M.)	P.C.C. DRIVEWAY 150mm (S.M.)	P.C.C. DRIVEWAY 200mm (S.M.)	TEMP. ACCESS (COMMERCIAL ENTRANCE) (EACH)	TEMP. ACCESS (PRIVATE ENTRANCE) (EACH)	CORRUGATED MEDIAN (S.M.)	
9+460.6 LT TO																		
9+572.3 LT	188				10.7		140	26.4	11.5						1			
BLDG #11	118																	
BLDG #12	216																	
BLDG #15	90																	
BLDG #19	842	76.5																CORRUGATED MEDIAN
BLDG #21	130																	
BLDG #22	116																	
BLDG #23	110																	(S.M.)
9+694.27 LT	22				3.6	63		11.9								1		
9+726.85 LT	58				9.4	63		11.9								1		
9+763.73 LT	50				3.6	30.5		5.8								1		
9+780.72 LT	131.5																	
9+779.56 RT	57.5	8			3.6	33.5		6.3								1		
9+815.04 RT	53.5				5.8	32.5		6.1								1		
9+823.46 LT					5.3		52	9.8							1			
9+845.46 RT	125.5				5.5	94		17.8								1		
9+919.63 RT	140				8.8	129		24.4								1		
10+175.48 LT	114.5	16			7.3		137	25.9	14						1			
SUBTOTAL	2562.5	100.5	0	0		445.5	329	146.3	25.5	0	0	0	0	0	3	7		0
CORTLAND																		
RT	38		13		6.9		32.1	6	9						1			
SUBTOTAL	38	0	13	0		0	32.1	6	9	0	0	0	0	0	1	0		0
RTE. 12																		
21+116.06 RT	54		23						18						1			
21+259.31 RT	76.5	24			7.4		55.5	10.5	15						1			
21+298.88 RT	151	27			10.7		88	17	11						1			
21+365.79 LT	86		19		206.7					13				90.3	1			5.9
21+395.00 LT	108		23.5						10.7									
21+502.29 RT	72		15		9.9		78	14.6		15.5					1			
21+555.13 RT	120		34		11.3		115.5	21.8		34					1			
21+565.24 LT	173	30			10.5		155	29	27						1			
21+639.57 LT	202	37			11		159	30	27.5						1			
21+662.62 RT	100		28.5		11.9					30					1			
21+730.29 LT	85		25		8.4		75	14.2	17						1			
21+799.31 LT	88	23			9		78	14.6	16						1			
SUBTOTAL	1315.5	141	168	0		0	804	151.7	124.2	110.5	0	0	0	189.8	11	0		5.9
MAIN ST.- WEST																		
50+024.00 LT	61																	
50+051.00 RT	49																	
50+127.63 LT	34				2.9	41.4		7.8								1		
SUBTOTAL	144	0	0	0		41.4	0	7.8	0	0	0	0	0	0	0	1		0
MEADOW LN.																		
0+023.24 LT	32.2				3.3	40		7.6								1		
0+045.22 LT	34.8				6.4	36.2		6.8								1		
0+052.12 RT	60.3				4	27.4		5.2								1		
SUBTOTAL	127.3	0	0	0		103.6	0	19.6	0	0	0	0	0	0	0	3		0
PRAIRIE ST.																		
0+016.80 RT	49.7																	
0+018.03 LT	176.8																	
0+041.50 RT	19.9				2.9	14.1		2.7								1		
0+053.87 LT	25.8				5.1	26		4.9								1		
SUBTOTAL	272.2	0	0	0		40.1	0	7.6	0	0	0	0	0	0	0	2		0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 22  
FROM US RTE 12 TO BUESCHING RD  
SCHEDULE OF QUANTITIES

SCALE :  
DATE : 07/21/04

DESIGNED BY JRP  
CHECKED BY DDL