

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	42
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

### DRIVEWAY SCHEDULE

60997

LOCATION	DRIVEWAY PAVEMENT REMOVAL (S.M.)	CURB REMOVAL (METER)	CURB & GUTTER REMOVAL (METER)	P.C.C. MEDIAN REMOVAL (S.M.)	DRIVEWAY WIDTH E/P -E/P (METER)	BITUMINOUS BASE COURSE SUPERPAVE 150mm (S.M.)	BITUMINOUS BASE COURSE SUPERPAVE 200mm (S.M.)	BIT. CONC. SURF. CSE., SUPERPAVE MIX. "C", N50 50mm (M TON)	TYPE B CURB (METER)	CURB & GUTTER TYPE B-15.30 (METER)	CURB & GUTTER TYPE B-15.15 (METER)	P.C.C. MEDIAN (S.M.)	P.C.C. DRIVEWAY 150mm (S.M.)	P.C.C. DRIVEWAY 200mm (S.M.)	TEMP. ACCESS (COMMERCIAL ENTRANCE) (EACH)	TEMP. ACCESS (PRIVATE ENTRANCE) (EACH)	CORRUGATED MEDIAN (S.M.)	
OLD RAND RD.																		
70+870.37 LT	39.5				9.8	49		9.3								1		
70+893.44 LT	16				2.7	19.6		3.7								1		
70+912.32 LT	18				4	24		4.5								1		
70+924.55 RT	82.5				7				6.5					23.6	1			
70+946.32 LT	41.5				6								40.3		1			
70+950 LT TO																		
70+993 LT	293																	
71+050.00 RT	113.5		34.5		9.6		111	21		24					1			
71+054 LT TO																		
71+100 LT	272																	
71+038.77 LT	218				7.6		50	9.5	6						1			
71+061.81 LT					11		71	13.4	5.5						1			
71+135.53 LT	62				7.6		19	3.6	5.2						1			
71+150.83 RT					8.3		19.5	3.7	5						1			
71+164.06 RT	81				8.5		22.5	4.3							1			
71+176.66 RT	69				8.5		21.5	4.1							1			
71+175.00 LT	59				37.2		77	14.5							1			
SUBTOTAL	1365	0	34.5	0		92.6	391.5	91.6	28.2	24	0	0	0	63.9	10	3	0	
MAIN ST.- EAST																		
90+047.36 RT	42.5				6.3		21.3	4							1			
90+053.14 LT	62				4.9	56.5		10.7								1		
90+090.94 LT	56				3.7	45		8.5								1		
90+103.60 RT	92.5				10.9		24.5	4.6							1			
90+105.44 LT	41.5				3	23		4.4								1		
90+124.02 LT	60				3.2	31		5.9								1		
90+200.98 LT	35				6	50		9.4	14.5							1		
90+219.81 RT	281				7.4		89	16.8	13.5						1			
90+223 RT	262																	
90+238 LT	409		11															
SUBTOTAL	1341.5	0	11	0		205.5	134.8	64.3	28	0	0	0	0	0	3	5	0	
CAROLYN CT.																		
110+019.50 LT	30				6.3	41.5		7.8	7.5							1		
SUBTOTAL	30	0	0	0		41.5	0	7.8	7.5	0	0	0	0	0	0	1	0	
BUESCHING RD																		
100+039.7	228														1			
SUBTOTAL	228	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	
MOHAWK TR.																		
9+686.30mRT	9.5				6.4		89.5	16.9								1		
SUBTOTAL	9.5	0	0	0		0	89.5	16.9	0	0	0	0	0	0	0	1	0	
TOTAL	18018	742	738.4	47		970.2	3510.4	844.5	520.9	349	65.5	78.5	0	340.2	53	23	5.9	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 22 FROM US RTE 12 TO BUESCHING RD SCHEDULE OF QUANTITIES
NAME	DATE	
		SCALE : DATE : 07/21/04 DESIGNED BY JRP CHECKED BY DDL