F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	45
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

60997

EXISTING SIGN SCHEDULE

EXISTING LOCATION	DESCRIPTION	RELOCATED LOCATION	REMOVE SIGN PANEL ASSEMBLY, TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY, TYPE B (EACH)	REMOVE SIGN PANEL, TYPE 1 (SM)	REMOVE SIGN PANEL, TYPE 2 (SM)	RELOCATE SIGN PANEL ASSEMBLY, TYPE A (EACH)	RELOCATE SIGN PANEL ASSEMBLY, TYPE B (EACH)	RELOCATE SIGN PANEL, TYPE 1 (SM)	RELOCATE SIGN PANEL, TYPE 2 (SM)	METAL POST, TYPE A (METER)	METAL POST, TYPE B (METER)	WOOD SIGN SUPPORT (METER)
GENESEE ST.													
8+940 RT	END TRUCK ROUTE		1										
8+945 RT	BEGIN TRUCK ROUTE		1										
8+967 RT	SPEED LIMIT 30		1										
9+033 RT	NO RIGHT TURN		1										
9+050 RT	STREET NAME SIGN		1										
9+060 RT	STOP		1										
9+123 RT	NO PARKING		1										
9+160 RT	NO RIGHT TURN		1										
9+166 RT	STREET NAME SIGN		1										
9+175 RT	STOP		1										
9+232 RT	END TRUCK ROUTE		1										
9+246 LT	SPEED LIMIT 30		1										
9+275 LT	BEGIN TRUCK ROUTE		1										
9+276 RT	STOP		1										
9+283 LT	STREET NAME SIGN		1										
OLD RAND RD.													
70+878 LT	CHEVRON		1										
70+898 LT	CHEVRON		1										
70+902 RT	LIBRARY	70+902 RT					1				4		
70+916 LT	CHEVRON		1										
70+931 LT	NO LEFT TURN	70+931 LT					1				3.8		
71+035 RT	RAILROAD CROSSING		1										
71+068 RT	FIRE TRUCK ENTRANCE	71+068 RT					1						4.6
71+103 LT	SPEED LIMIT 30		1										
71+147 RT	SPEED LIMIT 25		1										
MAIN EAST													
90+057 RT	RAILROAD CROSSING		1										
90+086 LT	SCHOOL CROSSING	90+086 LT					1					4.1	
60+151 LT	DO NOT STOP ON TRACKS		1										
CAROLYN CT.													
110+026 LT	RAILROAD CROSSING		1										
110+060 LT	STOP		1										
MOHAWK TR.													
9+650 RT	NO PARKING		1										
9+655 RT	ROAD CLOSED AHEAD		1										
9+670 RT	SPEED LIMIT 20		1										
9+676 LT	DEAD END		1										
9+691 LT	STOP		1										
BUESCHING RD.													
100+077 LT	CHURCH SIGN	100+077 LT						1					5
100+129 RT	DEAD END	100+129 RT					1						4.4
100+138 RT	NO PARKING	100+138 RT					1				3.7		
100+147 RT	SPEED LIMIT 20	100+147 RT					1				3.8		
SUBTOTAL			30	0	0	0	7	1	0	0	15.3	4.1	14
TOTAL			79	13	3.52	3.2	23	4	5.04	0	26.7	45.2	43.5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD

SCALE :
DATE : 07/21/04

DESIGNED BY
CHECKED BY