

#60997

MAINTENANCE OF TRAFFIC / TEMPORARY DRAINAGE SCHEDULE

PAY ITEM	UNIT	STAGE 1A				STAGE 1B			
		ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL	ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL
TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	153	0	1705	1858	6483	0	2156	8639
TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	0	0	31	31	566	0	46	612
TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	0	0	106	106	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	42	0	0	42	166	0	37	203
PAVEMENT MARKING TAPE TYPE III - LINE 100MM	METER	0	0	195	195	692	0	1491	2183
PAVEMENT MARKING TAPE TYPE III - LINE 150MM	METER	0	0	0	0	0	0	258	258
PAVEMENT MARKING TAPE TYPE III - LINE 300MM	METER	0	0	8	8	0	0	0	0
PAVEMENT MARKING TAPE TYPE III - LINE 600MM	METER	0	0	0	0	0	0	25	25
PAVEMENT MARKING REMOVAL	SQ M	40	0	230	270	554	0	256	810
TEMPORARY PAVEMENT	SQ M	162	2448	1333	3943	2944	0	4225	7169
TEMPORARY CONCRETE BARRIER	METER				0	107		129	236
IMPACT ATTENUATOR TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH				0	1		1	2
CATCH BASINS TO BE ADJUSTED	EACH				0	2		1	3
MANHOLES TO BE ADJUSTED	EACH			1	1	2			2
FRAMES AND GRATES TO BE REMOVED	EACH			1	1	4		1	5
TEMPORARY MANHOLES, TYPE A, 1.5 m DIA, TYPE 1 FRAME, OPEN LID	EACH				0			1	1
TEMPORARY MANHOLES, TYPE A, 1.5 m DIA, TYPE 1 FRAME, CLOSED LID	EACH	3			3			1	1
TEMPORARY INLET	EACH			2	2	7		1	8
TEMPORARY STORM SEWER, 300 mm	EACH	14.4		7.2	21.6	56.4		1.2	57.6
END SECTIONS TO BE RELOCATED	EACH				0	1			1
FRAMES AND GRATES TO BE REMOVED AND REPLACED WITH TYPE 1 FRAME, OPEN LID	EACH			1	1			3	3
TYPE 1 FRAME, OPEN LID (TEMPORARY)	EACH				0			15	15

PAY ITEM	UNIT	STAGE 2A				STAGE 2B			
		ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL	ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL
TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	6979	3568	3292	13839	1855	0	0	1855
TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	0	330	0	330	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	0	0	0	0	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	108	66	14	188	50	0	0	50
PAVEMENT MARKING TAPE TYPE III - LINE 100MM	METER	312	3312	1306	4930	0	0	434	434
PAVEMENT MARKING TAPE TYPE III - LINE 150MM	METER	0	0	214	214	0	0	0	0
PAVEMENT MARKING TAPE TYPE III - LINE 300MM	METER	0	0	0	0	0	0	0	0
PAVEMENT MARKING TAPE TYPE III - LINE 600MM	METER	0	21	21	42	0	0	14	14
PAVEMENT MARKING REMOVAL	SQ M	872	191	158	1221	200	0	0	200
TEMPORARY PAVEMENT	SQ M		4333	2022	6355	1420			1420
MANHOLES TO BE ADJUSTED	EACH		4		4				0
TEMPORARY END SECTION	EACH			1	1				0
TEMPORARY INLET	EACH			4	4				0
TEMPORARY STORM SEWER, 300 mm	EACH			183	183				0
FRAMES AND GRATES TO BE REMOVED AND REPLACED WITH TYPE 1 FRAME, OPEN LID	EACH		3		3				0
TYPE 1 FRAME, OPEN LID (TEMPORARY)	EACH			5	5				0
TEMPORARY CONCRETE BARRIER	METER	103			103				0
IMPACT ATTENUATOR TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	1			1	1			1
TEMPORARY CONCRETE BARRIER - RELOCATE	METER	107			107	103			103
IMPACT ATTENUATOR TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3 - RELOCATE	EACH	1			1	1			1

REVISIONS	
NAME	DATE
REVISOR GEOMETRY	11/24/04
FROM STA. 6+922.366 TO STA. 7+440.820	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 22  
FROM US RTE 12 TO BUESCHING RD  
MAINTENANCE OF TRAFFIC  
SCHEDULE OF QUANTITIES  
DRAWN BY MBF  
CHECKED BY SMK  
DATE 7/21/04