

#60997

SEDIMENT CONTROL, SILT FENCE SCHEDULE

LOCATION	METER												
	STAGE 1A	STAGE 1B	STAGE 2A	STAGE 2B	STAGE 3A	STAGE 3B	STAGE 4A	STAGE 4B	STAGE 5A	STAGE 5B	STAGE 5C	STAGE 6A	STAGE 6B
ILL. RT. 22 - BEGINNING TO U.S. RT 12 (RAND RD.)	110	435	285	0	0	320	500	0	0	0	0	500	0
ILL. RT. 22 - U.S. RT 12 (RAND RD.) TO MAIN ST. WEST	0	0	0	0	0	300	465	0	0	0	0	465	0
ILL. RT. 22 - MAIN ST. WEST TO OLD RAND RD.	1381	0	0	0	155	0	0	0	0	0	0	0	0
ILL. RT. 22 - OLD RAND RD. TO END	514	0	211	0	187	0	0	0	0	0	0	0	0
U.S. RT. 12 (RAND RD.)	0	0	130	0	230	30	0	0	0	0	70	0	0
MAIN ST. WEST (OLD ILL. RT. 22)	0	0	0	0	0	0	0	0	0	0	0	0	0
OLD RAND RD.	0	0	0	0	273	0	0	0	0	0	0	0	0
MAIN ST. EAST	44	0	0	0	0	0	0	0	0	0	0	190	161
BEUSCHING RD.	0	0	0	0	0	0	0	0	0	0	0	0	0
STAGE TOTALS	2049	435	626	0	845	650	965	0	0	0	70	1155	161
PROJECT TOTAL													6956

QUANTITY PROVIDED FOR PERIMETER EROSION BARRIER (METER) AT EVERY LOCATION WHERE WATER LEAVES THE CONSTRUCTION AREA.

TEMPORARY EROSION CONTROL SEEDING SCHEDULE

LOCATION	KG												
	STAGE 1A	STAGE 1B	STAGE 2A	STAGE 2B	STAGE 3A	STAGE 3B	STAGE 4A	STAGE 4B	STAGE 5A	STAGE 5B	STAGE 5C	STAGE 6A	STAGE 6B
ILL. RT. 22 - BEGINNING TO U.S. RT 12 (RAND RD.)	13	37	0	0	0	0	0	0	0	0	0	0	0
ILL. RT. 22 - U.S. RT 12 (RAND RD.) TO MAIN ST. WEST	71	35	0	0	0	16	0	0	0	0	0	0	0
ILL. RT. 22 - MAIN ST. WEST TO OLD RAND RD.	32	0	16	0	4	0	0	0	0	0	0	0	0
ILL. RT. 22 - OLD RAND RD. TO END	20	0	20	0	6	0	0	0	0	0	0	0	0
U.S. RT. 12 (RAND RD.)	38	8	32	0	0	0	0	0	0	0	0	0	0
MAIN ST. WEST (OLD ILL. RT. 22)	10	0	0	0	0	0	5	0	0	0	0	0	0
OLD RAND RD.	0	0	4	0	12	0	0	0	0	0	0	0	0
MAIN ST. EAST	1	0	0	0	0	0	0	0	0	0	0	0	3
BEUSCHING RD.	0	0	6	0	0	0	0	0	0	0	0	0	0
STAGE TOTALS	185	80	78	0	22	16	5	0	0	0	0	0	3
PROJECT TOTAL													389

QUANTITY PROVIDED FOR TEMPORARY EROSION CONTROL SEEDING (KG) AT EVERY PROPOSED LOCATION WHERE SOIL WILL BE DISTURBED BY CONSTRUCTION ACTIVITIES BUT PERMENENT EROSION CONTROL MEASURES HAVE NOT BEEN APPLIED.
APPLICATION RATE = 110 KG/HECTARE

DIVERSION CHANNEL SCHEDULE
(PAID FOR AS: EARTH EXCAVATION FOR EROSION CONTROL)

LOCATION	CU METERS	
STAGE 1A		
ILL. RT. 22 8+312 TO 8+440 LT	49	
ILL. RT. 22 8+457 TO 8+580 LT	47	
STAGE TOTAL	96	
PROJECT TOTAL		96

SLOPE DRAIN SCHEDULE
(PAID FOR AS: PIPE DRAINS 300MM)

LOCATION	METERS	
STAGE 1A		
ILL. RT. 22 8+430 LT	13.6	
ILL. RT. 22 8+490 LT	6.8	
STAGE TOTAL	20.4	
PROJECT TOTAL		20.4

NOTE: PERIMETER EROSION BARRIER, TEMPORARY DITCH CHECKS AND INLET AND PIPE PROTECTION WILL BE CONSTRUCTED AS SHOWN ON STANDARD 280001 AND AS DIRECTED BY THE ENGINEER. MAINTENANCE AND CLEANING OF THE EROSION CONTROL ITEMS WILL BE INCLUDED IN THE RESPECTIVE EROSION CONTROL PAY ITEMS.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 22 FROM US RTE 12 TO BUESCHING RD TEMPORARY EROSION CONTROL PLANS SCHEDULE OF QUANTITIES
NAME	DATE	
REVISOR'S MARK		DRAWN BY RLS CHECKED BY MBF DATE 7/21/04
REVISED GEOMETRY	11/24/04	
FROM STA. 6+922.366 TO		
STA. 7+440.820		