F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1337	19R-1	LAKE	800	226
F.STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

#60997

LEGEND
- PAVEMENT REMOVAL
- DRIVEWAY, SIDEWALK & MEDIAN REMOVAL
- BIT SURF REMOVAL
- BIT SURF REM BUTT JT
- C & G REM
- 10" TREE REMOVAL

EXISTING PLAN

PROPOSED ILLINOIS ROUTE 22

PROP. CURVE 619
PI STA = 8+290.299
Δ = 25° 52' 02" (LT)
R = 260.906 m
T = 59.916 m
L = 117.790 m
E = 6.791 m
T.R. =24 m
S.E. = 3.5%
S.E.RUN. = 41 m
P.C.C. STA = 8+230.383
P.T. STA = 8+348.173

REVISIONS	
NAME	DATE
⚠ CURVE DATA 619	11/24/04
"E", "TR" AND "SE RUN" FILLED OUT	

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
PLAN AND PROFILE
STA. 8+050 TO STA. 8+350

SCALE: 1:500 HORIZ. 1:50 VERT.
DATE: 09/24/04
DRAWN BY:
CHECKED BY: