


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	355
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

WATER MAIN RELOCATION

Station	to	Station	Fire Hydrant w/ Auxiliary Valve & Valve Box	Domestic Water Service Boxes	Removal and Disposal of Unsuitable Material	Porous Granular Embankment, Subgrade	Trench Backfill	Exploration Trench Special	Ductile Iron Water Main 150MM	Ductile Iron Water Main 200MM	Ductile Iron Water Main 250MM	Ductile Iron Water Main 300MM	Water Valves 150MM	Water Valves 200MM	Water Valves 250MM	Water Valves 300MM	Adjusting Water Main 300MM	
			56400820	56500800	M2021200	M2070420	M2080150	M2130010	M5610415	M5610420	M5610425	M5610430	M5610635	M5610640	M5610645	M5610650	M5610430	
			Each	Each	Cu M	Cu M	Cu M	Meter	Meter	Meter	Meter	Meter	Each	Each	Each	Each	Meter	
ILLINOIS ROUTE 22																		
STA	7+200	to	STA	7+500	0		0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0.0	
STA	7+500	to	STA	7+750	0		69.0	0.0	1.0	0.0	180.3	0.0	0	0	0	0	0.0	
STA	7+750	to	STA	8+050	1		499.9	0.0	14.4	2.3	316.8	0.0	1	1	4	0	0.0	
STA	8+050	to	STA	8+350	0		376.3	0.0	13.5	0.0	0.0	200.6	0	0	0	0	10.0	
STA	8+350	to	STA	8+650	0		36.9	0.0	4.5	0.0	0.0	222.3	0	0	0	2	0.0	
STA	8+650	to	STA	8+950	0		0.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0.0	
STA	8+950	to	STA	9+200	1		266.7	0.0	25.2	0.0	0.0	260.6	2	0	0	2	0.0	
STA	9+200	to	STA	9+500	0		53.4	0.0	7.9	0.0	0.0	69.8	1	0	0	2	0.0	
STA	9+500	to	STA	9+800	0		124.9	10.0	8.1	0.0	0.0	203.0	1	0	0	0	0.0	
STA	9+800	to	STA	10+100	1		311.4	0.0	48.5	3.8	0.0	316.8	0	1	1	2	0.0	
STA	10+100	to	STA	10+200	0		23.1	0.0	1.0	150.2	0.0	0.0	0	1	0	0	0.0	
U.S. ROUTE 12 (RAND ROAD)																		
STA	21+150	to	STA	21+423.511														
STA	21+423.511	to	STA	21+700	0		0.0	0.0	1.0	0.0	0.0	0.0	0	0	0	0	0.0	
STA	21+700	to	STA	22+000	0		0.0	0.0	1.0	0.0	0.0	0.0	0	0	0	0	0.0	
OLD RAND ROAD																		
STA	70+835	to	STA	71+000	1		79.3	0.0	4.0	6.0	0.0	65.3	0	1	0	1	0.0	
STA	71+000	to	STA	71+200	1		185.7	0.0	5.4	11.1	0.0	153.4	0	0	0	1	0.0	
MAIN STREET WEST																		
STA	50+000	to	STA	50+200	1		70.0	0.0	61.6	0.0	0.0	86.2	0	0	0	1	0.0	
MAIN STREET EAST																		
STA	90+000	to	STA	90+280	0		24.5	0.0	27.5	5.8	0.0	0.0	0	0	0	0	0.0	
PROJECT CONTINGENCY					20	100.0	100.0	40.0	80.0				2				10.0	
TOTAL =				6	20	100.0	100.0	2121.1	50.0	224.6	259.2	497.1	1578.0	5	6	5	11	20.0

DATE	BY
SURVEYED	
PLOTTED	
TEMPLATE	
AREAS CHECKED	
NO.	

DATE	BY
ORIGINAL SURVEY	
NOTE BOOK	
AREAS CHECKED	
NO.	



THIS SEAL APPLIES TO ALL WATER MAIN AND SANITARY SEWER RELOCATION PLANS SHEETS 355 THROUGH 391-C, INCLUSIVE

REVISIONS	
NAME	DATE
Misc.	11/24/04

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD

SCHEDULES
WATER MAIN RELOCATION
SHEET 1 OF 4

DRAWN BY: JH
CHECKED BY: RS
DATE: 08/19/03