

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	374
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BY	DATE
FINAL SURVEY PLOTTED	
NOTE BOOK TEMPLATE AREAS CHECKED	
NO.	

BY	DATE
ORIGINAL SURVEY PLOTTED	
NOTE BOOK TEMPLATE AREAS CHECKED	
NO.	

SANITARY SEWER RELOCATION

Station	to	Station	Removal and Disposal of Unsuitable Material	Porous Granular Embankment, Subgrade	Trench Backfill	Sanitary Manholes, 1.2M Diameter with Frame, Lid, and Chimney Seal	Drop Sanitary Manholes, 1.2M Diameter with Frame, Lid, and Chimney Seal	Sanitary Sewer, Ductile Iron Pipe, 300MM Diameter	Controlled Low Strength Material	Sanitary Sewer 150MM	Sanitary Sewer 200MM	Sanitary Sewer 250MM	Sanitary Sewer 300MM	Sanitary Sewer, Ductile Iron Pipe, 150MM Diameter	Sanitary Sewer, Ductile Iron Pipe, 200MM Diameter			
			M2021200	M2070420	M2080150	MX030314	MX030315	MX030393	MZ013825	MZ056800	MZ056900	MZ057000	MZ057100					
			Cu M	Cu M	Cu M	Each	Each	Meter	Cu M	Meter	Meter	Meter	Meter	Meter	Meter			
ILLINOIS ROUTE 22																		
STA	7+200	to	STA	7+500		0.0	2	1	47.0	0.0	0.0	0.0	7.9	0.0	0.0			
STA	7+500	to	STA	7+750		847.2	5	2	43.1	0.0	0.0	5.4	6.5	122.0	0.0			
STA	7+750	to	STA	8+050		440.0	5	4	36.3	0.0	0.0	6.3	0.0	264.1	0.0			
STA	8+050	to	STA	8+350		408.2	1	0	0.0	0.0	0.0	0.0	76.9	0.0	0.0			
STA	8+350	to	STA	8+650														
STA	8+650	to	STA	8+950														
STA	8+950	to	STA	9+200		837.8	5	1	0.0	0.0	220.4	0.0	0.0	0.0	76.9			
STA	9+200	to	STA	9+500														
STA	9+500	to	STA	9+800		75.3	2	0	0.0	20.0	0.0	0.0	0.0	0.0	44.3			
STA	9+800	to	STA	10+100		26.6	3	0	0.0	0.0	0.0	50.0	0.0	0.0	0.0			
STA	10+100	to	STA	10+200		49.3	3	1	0.0	0.0	13.4	100.0	0.0	0.0	0.0			
LIFT STATION																		
STA	7+450		STA			200.0	4	0	0.0	70.0	0.0	0.0	0.0	0.0	0.0			
FORCE MAIN, LIFT STATION TO RTE 12																		
STA	30+000	to	STA	30+300		720.6	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0			
U.S. ROUTE 12 (RAND ROAD)																		
STA	21+423.511	to	STA	21+700		83.8	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0			
STA	21+700	to	STA	22+000		67.3	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0			
PROJECT CONTINGENCY						400.0	400.0				30.0			30.0				
TOTAL =						400.0	400.0	3756.1	30.0	9.0	126.4	70.0	50.0	245.5	156.5	470.9	30.0	127.1

REVISIONS	
NAME	DATE
Misc	11/24/04

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 22  
FROM US RTE 12 TO BUESCHING RD

SCHEDULES  
SANITARY SEWER RELOCATION  
SHEET 1 OF 3

DATE: 08/19/03

DRAWN BY: JH

CHECKED BY: RS