

|                     |            |                           |              |           |
|---------------------|------------|---------------------------|--------------|-----------|
| F.A.I. RTE.         | SECTION    | COUNTY                    | TOTAL SHEETS | SHEET NO. |
| 55                  | 2002-022 K | WILL                      | 172          | 8         |
| STA. 10+00          |            | TO STA. 22+96.05          |              |           |
| FED. ROAD DIST. NO. |            | ILLINOIS FED. AID PROJECT |              |           |
| CONTRACT NO. 62389  |            |                           |              |           |

URBAN  
90% FED.  
10% STATE

| CODED PAY ITEM NO. | DESCRIPTION  | UNIT OF MEASURE | TOTAL QUANTITY | RAMP A  | RAMP B  | RAMP C  | RAMP D  | EXIT ONLY LN | ILL RTE 53 | TS S. RAMP | TS N. RAMP | LIGHTING | SIGNING | SURVEILLANCE |
|--------------------|--|-----------------|----------------|---------|---------|---------|---------|--------------|------------|------------|------------|----------|---------|--------------|
|                    |  |                 |                | J000-2A | J000-2A | J000-2A | J000-2A | 1000-2A      | J000-2A    | Y031-1F    | Y031-1F    | Y030-1E  | Y002-1C | Y032-1F      |
| 60618310           | CONCRETE MEDIAN SURFACE, 4 INCH                        | SQ FT           | 1466           | 423     | 272     | 208     | 563     |              |            |            |            |          |         |              |
| * 63000000         | STEEL PLATE BEAM GUARD RAIL, TYPE A                    | FOOT            | 680            |         | 312.5   |         |         | 367.5        |            |            |            |          |         |              |
| * 63100085         | TRAFFIC BARRIER TERMINAL, TYPE 6                       | EACH            | 5              |         | 2       |         |         | 2            | 1          |            |            |          |         |              |
| * 63100105         | TRAFFIC BARRIER TERMINAL, TYPE 10                      | EACH            | 1              |         | 1       |         |         |              |            |            |            |          |         |              |
| * 63100167         | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)     | EACH            | 1              |         | 1       |         |         |              |            |            |            |          |         |              |
| 63200310           | GUARDRAIL REMOVAL                                      | FOOT            | 870            |         | 604     |         |         | 266          |            |            |            |          |         |              |
| X6370930           | CONCRETE BARRIER, DOUBLE FACE, 32 HT                   | FOOT            | 916            |         | 446     |         |         | 470          |            |            |            |          |         |              |
| X6370910           | CONCRETE BARRIER, SINGLE FACE, 32 HT                   | FOOT            | 76             |         | 76      |         |         |              |            |            |            |          |         |              |
| 63700805           | CONCRETE BARRIER TRANSITION                            | FOOT            | 406            |         | 76      |         |         | 330          |            |            |            |          |         |              |
| 64200105           | SHOULDER RUMBLE STRIP                                  | FOOT            | 228            |         |         |         |         | 228          |            |            |            |          |         |              |
| 66400525           | CHAIN LINK FENCE, 4' ATTACHED TO STRUCTURE             | FOOT            | 1936           |         | 1936    |         |         |              |            |            |            |          |         |              |
| 67000400           | ENGINEER'S FIELD OFFICE, TYPE A                        | CAL MO          | 12             |         | 12      |         |         |              |            |            |            |          |         |              |
| 67100100           | MOBILIZATION   | L SUM           | 1              |         | 1       |         |         |              |            |            |            |          |         |              |
| 66410300           | CHAIN LINK FENCE REMOVAL                               | FOOT            | 995            |         | 995     |         |         |              |            |            |            |          |         |              |
| * 66900200         | NON-SPECIAL WASTE DISPOSAL                             | CU YD           | 893            |         | 893     |         |         |              |            |            |            |          |         |              |
| * 66900450         | SPECIAL WASTE PLANS AND REPORT                         | L SUM           | 1              |         | 1       |         |         |              |            |            |            |          |         |              |
| * 66900530         | SOIL DISPOSAL ANALYSIS                                 | EACH            | 1              |         | 1       |         |         |              |            |            |            |          |         |              |
| X0301766           | DRILL AND GROUT #6 TIE BARS                            | EACH            | 2034           |         | 295     |         |         | 1150         | 589        |            |            |          |         |              |
| X0322118           | REMOVE CONCRETE FLARED END SECTIONS                    | EACH            | 5              |         | 5       |         |         |              |            |            |            |          |         |              |
| X0323426           | SEDIMENT CONTROL, DRAINAGE STRUCTURE                   | EACH            | 26             |         |         |         |         | 26           |            |            |            |          |         |              |
|                    | INLET FILTER CLEANING                                  |                 |                |         |         |         |         |              |            |            |            |          |         |              |
| X0712400           | TEMPORARY PAVEMENT                                     | SQ YD           | 442            | 127     |         |         | 316     |              |            |            |            |          |         |              |
| X6370890           | CONCRETE BARRIER, DOUBLE FACE, TYPE F                  | FOOT            | 1701           |         | 455     |         |         | 1246         |            |            |            |          |         |              |
| Z0000100           | ABANDON EXISTING CULVERT                               | EACH            | 1              |         | 1       |         |         |              |            |            |            |          |         |              |
| Z0041700           | PLUG EXISTING STORM SEWERS                             | EACH            | 4              |         | 2       |         |         |              | 2          |            |            |          |         |              |
| Z0076600           | TRAINERS   | PAIRS           | 1000           | 1000    |         |         |         |              |            |            |            |          |         |              |
| 70101800           | TRAFFIC CONTROL AND PROTECTION (SPECIAL)               | L SUM           | 1              | 0.1     | 0.2     | 0.1     | 0.1     | 0.3          | 0.2        |            |            |          |         |              |
| 70300510           | PAVEMENT MARKING TAPE, TYPE III                        | SQ FT           | 1051           |         | 426     |         | 188     |              | 437        |            |            |          |         |              |
|                    | LETTERS AND SYMBOLS                                    |                 |                |         |         |         |         |              |            |            |            |          |         |              |
| 70300520           | PAVEMENT MARKING TAPE, TYPE III 4"                     | FOOT            | 27409          | 690     | 5756    | 339     | 1956    | 13150        | 5518       |            |            |          |         |              |
| 70300530           | PAVEMENT MARKING TAPE, TYPE III 5"                     | FOOT            | 3970           |         | 120     |         | 50      | 1940         | 1860       |            |            |          |         |              |
| 70300540           | PAVEMENT MARKING TAPE, TYPE III 6"                     | FOOT            | 2060           |         | 503     |         | 363     |              | 1194       |            |            |          |         |              |
| 70300550           | PAVEMENT MARKING TAPE, TYPE III 8"                     | FOOT            | 1609           | 213     | 267     | 155     | 345     | 629          |            |            |            |          |         |              |
| 70300560           | PAVEMENT MARKING TAPE, TYPE III 12"                    | FOOT            | 1560           |         | 215     |         | 928     | 47           | 370        |            |            |          |         |              |
| 70300570           | PAVEMENT MARKING TAPE, TYPE III 24"                    | FOOT            | 207            |         | 128     |         | 79      |              |            |            |            |          |         |              |
| 70301000           | WORK ZONE PAVEMENT MARKING REMOVAL                     | SQ FT           | 37866          | 903     | 7415    | 494     | 3909    | 15766        | 9379       |            |            |          |         |              |
| 70400100           | TEMPORARY CONCRETE BARRIER                             | FOOT            | 6144           |         | 2339    |         |         | 3805         |            |            |            |          |         |              |
| 70400200           | RELOCATE TEMPORARY CONCRETE BARRIER                    | FOOT            | 4132           |         | 1224    |         |         | 2908         |            |            |            |          |         |              |
| * 78008200         | POLYUREA PAVEMENT MARKING TYPE I                       | SQ FT           | 1302           |         | 437     |         | 146     | 218          | 501        |            |            |          |         |              |
|                    | LETTERS AND SYMBOLS                                    |                 |                |         |         |         |         |              |            |            |            |          |         |              |
| * 78008210         | POLYUREA PAVEMENT MARKING TYPE I - LINE 4"             | FOOT            | 12751          | 511     | 1161    | 221     | 1188    | 7820         | 1850       |            |            |          |         |              |
| * 78008220         | POLYUREA PAVEMENT MARKING TYPE I - LINE 5"             | FOOT            | 5133           |         | 803     |         |         | 3360         | 970        |            |            |          |         |              |
| * 78008230         | POLYUREA PAVEMENT MARKING TYPE I - LINE 6"             | FOOT            | 4140           |         | 197     |         |         |              | 3943       |            |            |          |         |              |
| * 78008240         | POLYUREA PAVEMENT MARKING TYPE I - LINE 8"             | FOOT            | 6475           | 155     | 1395    | 112     | 336     | 3831         | 646        |            |            |          |         |              |
| * 78008250         | POLYUREA PAVEMENT MARKING TYPE I - LINE 12"            | FOOT            | 1145           | 14      | 400     | 13      | 67      | 303          | 348        |            |            |          |         |              |
| * 78008270         | POLYUREA PAVEMENT MARKING TYPE I - LINE 24"            | FOOT            | 396            | 25      | 66      | 23      | 66      |              | 216        |            |            |          |         |              |
| * 78100100         | RAISED REFLECTIVE PAVEMENT MARKER                      | EACH            | 398            |         | 105     |         |         | 197          | 96         |            |            |          |         |              |
| * 78200100         | MONODIRECTIONAL PRISMATIC BARRIER                      | EACH            | 139            |         | 39      |         |         | 100          |            |            |            |          |         |              |
|                    | REFLECTOR  |                 |                |         |         |         |         |              |            |            |            |          |         |              |
| 78300200           | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL              | EACH            | 284            |         |         |         |         | 284          |            |            |            |          |         |              |
| X7013820           | TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS              | CAL DA          | 270            |         |         |         |         | 270          |            |            |            |          |         |              |
| X7011015           | TRAFFIC CONTROL AND PROTECTION, (EXPRESSWAYS)          | L.S.            | 1              |         |         |         |         | 1            |            |            |            |          |         |              |
| X7015050           | PORTABLE CHANGEABLE MESSAGE SIGN                       | CAL MO          | 24             |         |         |         |         | 12           | 12         |            |            |          |         |              |
| Z0030250           | IMPACT ATTENUATOR, TEMP (NON REDIRECTIVE) TEST LEVEL 3 | EACH            | 3              |         | 1       |         |         | 2            |            |            |            |          |         |              |
| Z0018500           | DRAINAGE STRUCTURES TO BE CLEANED                      | EACH            | 8              |         |         |         |         |              | 8          |            |            |          |         |              |
| X032411Z           | BARRIER BASE   | FOOT            | 1533           |         | 733     |         |         | 800          |            |            |            |          |         |              |

Δ SFTY-B/L V080  
□ NON-PARTICIPATING  
\* SPECIALTY ITEMS

PLAN SURVEYED BY DATE  
ALIGNED CHECKED BY DATE  
NOTE BOOK NO. FILE NAME

PROFILE SURVEYED BY DATE  
GRADES CHECKED BY DATE  
STRUCTURE NOTATION CHD

|           |      |  |                                |
|-----------|------|--|--------------------------------|
| REVISIONS |      | ILLINOIS DEPARTMENT OF TRANSPORTATION<br><br>SUMMARY OF QUANTITIES<br><br>SCALE: NTS<br>DATE: 1/4/2005 | DRAWN BY: CC<br>CHECKED BY: RI |
| NAME      | DATE |  |                                |
|           |      |  |                                |
|           |      |  |                                |
|           |      |  |                                |
|           |      |  |                                |
|           |      |  |                                |
|           |      |  |                                |
|           |      |  |                                |
|           |      |  |                                |

**DMJM HARRIS**  
303 East Wacker Drive, Suite 600  
Chicago, Illinois, 60601 Phone: 312.321.6101 Fax: 312.396.2392