



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 1, 2005

SUBJECT: FAI Route 90/94
Project IM-094-3(380)056)
Section 2004-071RS
Cook County
Contract No. 62810
Item No. 3, March 11, 2005 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS: :

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 69 & 80 of the Special Provisions.
2. Revised page 2 of the Table of Contents.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger DE'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe; Roger Driskell; Jim White; Design & Environment File

TBW:TK:jc

CONTRACTOR CERTIFICATION STATEMENT41
COARSE AGGREGATE FOR TRENCH BACKFILL, BACKFILL AND BEDDING (BDE)..... 43
CONCRETE ADMIXTURES (BDE) 48
CURING AND PROTECTION OF CONCRETE CONSTRUCTION (BDE)..... 52
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... 59
EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)..... 65
FLAGGER VESTS (BDE)..... 66
FREEZE-THAW RATING (BDE) 66
FURNISHED EXCAVATION (BDE)..... 66
HAND VIBRATOR (BDE) 67
INLET FILTERS (BDE)..... 67
PARTIAL PAYMENTS (BDE)..... 69
PAVEMENT THICKNESS DETERMINATION FOR PAYMENT (BDE) 70
PAYMENTS TO SUBCONTRACTORS (BDE)..... 77
PERSONAL PROTECTIVE EQUIPMENT (BDE)..... 77
PORTABLE CHANGEABLE MESSAGE SIGNS (BDE)..... 78
PORTLAND CEMENT (BDE)..... 78
PORTLAND CEMENT CONCRETE (BDE)..... 79
PRECAST CONCRETE PRODUCTS (BDE) 79
PREFORMED RECYCLED RUBBER JOINT FILLER (BDE) 80
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE) 81
SUBGRADE PREPARATION (BDE)..... 82
SURFACE TESTING OF PAVEMENTS (BDE)..... 83
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)..... 89
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)..... 90
STEEL COST ADJUSTMENT (BDE) 91

Revised 03-01-2005

Inner Filter Bag		
Material Property	Test Method	Minimum Avg. Roll Value
Grab Tensile Strength	ASTM D 4632	45 kg (100 lb)
Grab Tensile Elongation	ASTM D 4632	50%
Puncture Strength	ASTM D 4833	29 kg (65 lb)
Trapezoidal Tear	ASTM D 4533	20 kg (45 lb)
UV Resistance	ASTM D 4355	70% at 500 hours
Actual Open Size	ASTM D 1420	212 μ m (No. 70 sieve US)
Permittivity	ASTM D 4491	2.0/sec
Water Flow Rate	ASTM D 4491	5900 Lpm/sq m (145 gpm/sq ft)

- b. Outer Reinforcement Bag. The outer reinforcement bag shall be constructed of polyester mesh material that conforms to the following requirements:

Outer Reinforcement Bag		
Material Property	Test Method	Value
Content	ASTM D 629	Polyester
Weight	ASTM D 3776	155 g/sq m (4.55 oz/sq yd) \pm 15%
Whales (holes)	ASTM D 3887	7.5 \pm 2 holes/25 mm (1 in.)
Chorses (holes)	ASTM D 3887	15.5 \pm 2holes/25 mm (1 in.)
Instronball Burst	ASTM D 3887	830 kPa (120 psi) min.
Thickness	ASTM D 1777	1.0 \pm 0.1 mm (0.040 \pm 0.005 in.)

- (4) Certification. The manufacturer shall furnish a certification with each shipment of inlet filters, stating the amount of product furnished, and that the material complies with these requirements.”

PARTIAL PAYMENTS (BDE)

Effective: September 1, 2003

Revise Article 109.07 of the Standard Specifications to read:

“**109.07 Partial Payments.** Partial payments will be made as follows:

- (a) Progress Payments. At least once each month, the Engineer will make a written estimate of the amount of work performed in accordance with the contract, and the value

Revised 03-01-2005

For all other precast concrete products using Class PC concrete or other mixtures, portland cement replacement with fly ash or GGBF slag shall be approved by the Engineer. Class F fly ash shall not exceed 15 percent by mass (weight) of the total portland cement and Class F fly ash. Class C fly ash shall not exceed 20 percent by mass (weight) of the total portland cement and Class C fly ash. GGBF slag shall not exceed 25 percent by mass (weight) of the total portland cement and GGBF slag.

Concrete mix designs, for precast concrete products, shall not consist of portland cement, fly ash and GGBF slag.

Ready-Mixed Concrete. Delete the last paragraph of Article 1020.11(a) of the Standard Specifications.

Shipping. When a precast concrete product has attained the specified strength, the earliest the product may be loaded, shipped, and used is on the fifth calendar day. The first calendar day shall be the date casting was completed.

Acceptance. Products which have been lot or piece inspected and approved by the Department prior to July 1, 1999, will be accepted for use on this contract.

PREFORMED RECYCLED RUBBER JOINT FILLER (BDE)

Effective: November 1, 2002

Revise Article 503.02(c) of the Standard Specifications to read:

“(c) Preformed Expansion Joint Filler..... 1051”

Revise Article 637.02(d) of the Standard Specifications to read:

“(d) Preformed Expansion Joint Filler..... 1051”

Add the following Article to Section 1051 of the Standard Specifications:

“1051.10 Preformed Recycled Rubber Joint Filler. Preformed recycled rubber joint filler shall consist of ground tire rubber, free of steel and fabric, combined with ground scrap or waste polyethylene. It shall not have a strong hydrocarbon or rancid odor and shall meet the physical property requirements of ASTM D 1752. Water absorption by volume shall not exceed 5.0 percent.”

Revised 03-01-2005