



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

3/1/2005

SUBJECT: FAI Route 90/94
Project IM-094-3(382)056
Section 2004-072RS
Cook County
Contract No. 62811
Item No. 4, 3/11/2005 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 67, 77 & 78 of the Special Provisions.
2. Revised page ii of the Table of Contents.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, appearing to read 'Ted B. Walschleger', followed by the initials 'P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe; Roger Driskell; Jim White; Design & Environment File

TK/cah

FAI ROUTE 90/94 (DAN RYAN EXPRESSWAY)

SECTION: (2004-072RS)

COOK COUNTY

COARSE AGGREGATE FOR TRENCH BACKFILL, BACKFILL AND BEDDING (BDE)..... 25

STORM WATER POLLUTION PREVENTION PLAN.....31

CONTRACTOR CERTIFICATION STATEMENT44

CONCRETE ADMIXTURES (BDE)..... 46

CURING AND PROTECTION OF CONCRETE CONSTRUCTION (BDE)..... 50

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... 56

EPOXY COATING ON REINFORCEMENT (BDE)..... 63

EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)..... 63

EXPANSION JOINTS (BDE)..... 63

FLAGGER VESTS (BDE)..... 63

FREEZE-THAW RATING (BDE)..... 64

FURNISHED EXCAVATION (BDE)..... 64

HAND VIBRATOR (BDE)..... 65

INLET FILTERS (BDE)..... 65

PARTIAL PAYMENTS (BDE)..... 67

PAVEMENT THICKNESS DETERMINATION FOR PAYMENT (BDE)..... 68

PAYMENTS TO SUBCONTRACTORS (BDE)..... 74

PERSONAL PROTECTIVE EQUIPMENT (BDE)..... 74

PORTABLE CHANGEABLE MESSAGE SIGNS (BDE)..... 75

PORTLAND CEMENT (BDE)..... 75

PORTLAND CEMENT CONCRETE (BDE)..... 76

PRECAST CONCRETE PRODUCTS (BDE)..... 76

PREFORMED RECYCLED RUBBER JOINT FILLER (BDE)..... 77

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 78

SUBGRADE PREPARATION (BDE)..... 79

SURFACE TESTING OF PAVEMENTS (BDE)..... 80

TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)..... 86

WORK ZONE TRAFFIC CONTROL DEVICES (BDE)..... 86

STEEL COST ADJUSTMENT (BDE)..... 88

Revised 3/1/2005

Outer Reinforcement Bag		
Material Property	Test Method	Value
Content	ASTM D 629	Polyester
Weight	ASTM D 3776	155 g/sq m (4.55 oz/sq yd) ±15%
Whales (holes)	ASTM D 3887	7.5 ± 2 holes/25 mm (1 in.)
Chorses (holes)	ASTM D 3887	15.5 ± 2holes/25 mm (1 in.)
Instronball Burst	ASTM D 3887	830 kPa (120 psi) min.
Thickness	ASTM D 1777	1.0 ± 0.1 mm (0.040 ± 0.005 in.)

- (4) Certification. The manufacturer shall furnish a certification with each shipment of inlet filters, stating the amount of product furnished, and that the material complies with these requirements.”

PARTIAL PAYMENTS (BDE)

Effective: September 1, 2003

Revise Article 109.07 of the Standard Specifications to read:

“109.07 Partial Payments. Partial payments will be made as follows:

- (a) Progress Payments. At least once each month, the Engineer will make a written estimate of the amount of work performed in accordance with the contract, and the value thereof at the contract unit prices. The amount of the estimate approved as due for payment will be vouchered by the Department and presented to the State Comptroller for payment. No amount less than \$1000.00 will be approved for payment other than the final payment.

The failure to perform any requirement, obligation, or term of the contract by the Contractor shall be reason for withholding any progress payments until the Department determines that compliance has been achieved. Furthermore, progress payments may be reduced by liens filed pursuant to Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c).

- (b) Material Allowances. At the discretion of the Department, payment may be made for materials, prior to their use in the work, when satisfactory evidence is presented by the Contractor. Satisfactory evidence includes justification for the allowance (to expedite the work, meet project schedules, regional or national material shortages, etc.),

Revised 3/1/2005

Portland Cement Replacement. For precast concrete products using Class PC concrete or other mixtures, portland cement replacement with fly ash or ground granulated blast-furnace (GGBF) slag shall be governed by the AASHTO or ASTM standard specification referenced in the Standard Specifications.

For all other precast concrete products using Class PC concrete or other mixtures, portland cement replacement with fly ash or GGBF slag shall be approved by the Engineer. Class F fly ash shall not exceed 15 percent by mass (weight) of the total portland cement and Class F fly ash. Class C fly ash shall not exceed 20 percent by mass (weight) of the total portland cement and Class C fly ash. GGBF slag shall not exceed 25 percent by mass (weight) of the total portland cement and GGBF slag.

Concrete mix designs, for precast concrete products, shall not consist of portland cement, fly ash and GGBF slag.

Ready-Mixed Concrete. Delete the last paragraph of Article 1020.11(a) of the Standard Specifications.

Shipping. When a precast concrete product has attained the specified strength, the earliest the product may be loaded, shipped, and used is on the fifth calendar day. The first calendar day shall be the date casting was completed.

Acceptance. Products which have been lot or piece inspected and approved by the Department prior to July 1, 1999, will be accepted for use on this contract.

PREFORMED RECYCLED RUBBER JOINT FILLER (BDE)

Effective: November 1, 2002

Revise Article 503.02(c) of the Standard Specifications to read:

“(c) Preformed Expansion Joint Filler..... 1051”

Revise Article 637.02(d) of the Standard Specifications to read:

“(d) Preformed Expansion Joint Filler..... 1051”

Add the following Article to Section 1051 of the Standard Specifications:

“1051.10 Preformed Recycled Rubber Joint Filler. Preformed recycled rubber joint filler shall consist of ground tire rubber, free of steel and fabric, combined with ground scrap or waste polyethylene. It shall not have a strong hydrocarbon or rancid odor and shall meet the physical property requirements of ASTM D 1752. Water absorption by volume shall not exceed 5.0 percent.”

Revised 3/1/2005

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)

Effective: July 1, 2004

Definition. Self-consolidating concrete is a flowable mixture that does not require mechanical vibration for consolidation.

Usage. Self-consolidating concrete may be used for precast concrete products. The design and testing of a self-consolidating concrete mixture shall be according to Section 1020 of the Standard Specifications except as modified herein.

Materials. Materials shall conform to the following requirements:

- (a) Self-Consolidating Admixtures. The self-consolidating admixture system shall consist of either a high range water-reducing admixture only or a high range water-reducing admixture combined with a separate viscosity modifying admixture. The one or two component admixture system shall be capable of producing a flowable concrete that does not require mechanical vibration.

The high range water-reducing admixture shall comply with the requirements of AASHTO M 194, Type F.

The viscosity modifying admixture will be evaluated according to the test methods and mix design proportions referenced in AASHTO M 194, except the following physical requirements shall be met:

- (1) For initial and final set times, the allowable deviation of the test concrete from the reference concrete shall not be more than 1.0 hour earlier or 1.5 hours later.
 - (2) For compressive and flexural strengths, the test concrete shall be a minimum of 90 percent of the reference concrete at 3, 7 and 28 days.
 - (3) The length change of the test concrete shall be a maximum 135 percent of the reference concrete. However, if the length change of the reference concrete is less than 0.030 percent, the length change of the test concrete shall be a maximum 0.010 percentage units greater than the reference concrete.
 - (4) The relative durability factor of the test concrete shall be a minimum 80 percent.
- (b) Fine Aggregate. A fine aggregate used alone in the mix design shall not have an expansion greater than 0.30 percent per ASTM C 1260. For a blend of two or more fine aggregates, the resulting blend shall not have an expansion greater than 0.30 percent.

The aggregate blend expansion will be calculated as follows: