

F.A.I. SECTION COUNTY TOTAL SHEET	90/94 2004-072RS COOK 54 8
STA. TO STA.	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

62811

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL 10% STATE
				URBAN ROADWAY J000-2A
20200100	EARTH EXCAVATION	CU YD	110	110
20400800	FURNISHED EXCAVATION	CU YD	25	25
20700220	POROUS GRANULAR EMBANKMENT	CU YD	236	236
20800150	TRENCH BACKFILL	CU YD	17	17
28000510	INLET FILTERS	EACH	11	11
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SO YD	4,055	4,055
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	3,667	3,667
42001300	PROTECTIVE COAT	SO YD	4,439	4,439
44000100	PAVEMENT REMOVAL	SO YD	1,686	1,686
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	24	24
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,100	1,100
44000600	SIDEWALK REMOVAL	SO FT	6,407	6,407
Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	42	42
55100300	STORM SEWER REMOVAL 8"	FOOT	113	113
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	3	3
60235200	INLETS, TYPE A, TYPE 1 FRAME OPEN LID (CITY OF CHICAGO)	EACH	4	4
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5	5
60500040	REMOVING MANHOLES	EACH	2	2
60500050	REMOVING CATCH BASINS	EACH	2	2
60500060	REMOVING INLETS	EACH	7	7
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	1,100	1,100
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* X0322124	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	65	65
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	30	30
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	22	22
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SO FT	2,593	2,593
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	5	5
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	1,100	1,100
XX157200	CITY ELECTRIC MANHOLES TO BE ADJUSTED	EACH	3	3
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
20076600	TRAINERS	HOUR		
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	4	4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
51st ST TO 48th PL (WENTWORTH AVENUE)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: December 17, 2004 CHECKED BY: JAL



Δ NON-PARTICIPATING
⊖ -1080
* SPECIALTY ITEMS

10/23/2004 10:33:53 AM