F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-073RS	COOK	74	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62812

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY 90% FEDERAL 10% STATE J000-2A
20200100	EARTH EXCAVATION	CU YD	165	165
20700220	POROUS GRANULAR EMBANKMENT	CU YD	333	333
20800150	TRENCH BACKFILL	CU YD	72	72
28000510	INLET FILTERS	EACH	21	21
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	529	529
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	5,572	5,572
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	5,177	5,177
42001300	PROTECTIVE COAT	SQ YD	6,683	6,683
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	566	566
44000100	PAVEMENT REMOVAL	SQ YD	2,892	2,892
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	61	61
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,209	1,209
44000600	SIDEWALK REMOVAL	SQ FT	7,665	7,665
44000700	APPROACH SLAB REMOVAL	SQ YD	558	558
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20	20
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	50,390	50,390
55100300	STORM SEWER REMOVAL 8"	FOOT	141	141
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	7	7
60202605	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1
60235200	INLETS, TYPE A, TYPE 1 FRAME OPEN LID (CITY OF CHICAGO)	EACH	2	2
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6	6
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	11	11
60500050	REMOVING CATCH BASINS	EACH	7	7
60500060	REMOVING INLETS	EACH	1	1
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	1,044	1,044
63200310	GUARDRAIL REMOVAL	FOOT	229	229
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300510	PAVEMENT MARKING TAPE, TYPE III-LETTERS AND SYMBOLS	SQ FT	292	292
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	8,562	8,562
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	134	134
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,411	3,411

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5202, PHONE: (312) 938-0300

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
51st ST (WENTWORTH AVE AND WELLS ST)

SUMMARY OF QUANTITIES

SCALE: NONE | DRAWN BY: LC
DATE: December 23, 2004 | CHECKED BY: JAL

m:\p4468\chtn\4-cntr9\add_cntr9\8\sht\general\sq9b1601202a.sht
12/21/2004 3:16:29 PM