

SUMMARY OF QUANTITIES

URBAN
90% FED.
10% STA

F.A.I. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-074RS	COOK	63	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

62813

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY
				J000-2A
20200100	EARTH EXCAVATION	CU YD	122	122
20400800	FURNISHED EXCAVATION	CU YD	6	6
20700220	POROUS GRANULAR EMBANKMENT	CU YD	133	133
20800150	TRENCH BACKFILL	CU YD	21	21
28000510	INLET FILTERS	EACH	17	17
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B, 8"	SQ YD	4,459	4,459
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	17	17
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.15	0.15
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	4,033	4,033
42001300	PROTECTIVE COAT	SQ YD	4,651	4,651
44000100	PAVEMENT REMOVAL	SO YD	2,008	2,008
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	41	41
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,246	1,246
44000600	SIDEWALK REMOVAL	SO FT	7,633	7,633
48200010	BITUMINOUS SHOULDERS, 1 1/2"	SO YD	17	17
55100300	STORM SEWER REMOVAL 8"	FOOT	60	60
60202505	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 1 FRAME OPEN LID (CITY OF CHICAGO)	EACH	4	4
60202605	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 1 FRAME CLOSED LID (CITY OF CHICAGO)	EACH	1	1
60235200	INLETS, TYPE A, TYPE 1 FRAME OPEN LID (CITY OF CHICAGO)	EACH	2	2
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	5
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5	5
60500050	REMOVING CATCH BASINS	EACH	6	6
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	1,260	1,260
63200310	GUARDRAIL REMOVAL	FOOT	165	165
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
X0322124	STORM SEWERS (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	52	52
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	34	34
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	34	34
X0324669	STORM SEWERS, ESVCP, TYPE 2, 8"	FOOT	28	28
X0712400	TEMPORARY PAVEMENT	SO YD	163	163
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1
X6065740	CONCRETE MEDIAN SURFACE, 5" MODIFIED	SO FT	626	626
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	1,212	1,212

• DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59th ST TO 57th ST (WELLS STREET)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: PHP
DATE: December 17, 2004 CHECKED BY: JAL



12/17/2004 4:35:55 PM