

**CONTRACT NO. 62822**

LOCATION OF WORK:  
107th AVE.

CONSTRUCTION TYPE CODE  
I000

LOCATION OF WORK:  
107th ST.

CONSTRUCTION TYPE CODE  
I000

SUMMARY OF QUANTITIES			TOTAL
CODE NO.	ITEM	UNIT	QUANTITIES <i>URBAN</i>
20201006	GRADING AND SHAPING SHOULDERS	UNIT	235
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15
40600300	AGGREGATE (PRIME COAT)	TON	73
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	4
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600980	BITUMINOUS SURFACE REMOVAL -BUTT JOINT	SQ YD	36
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	276
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	36461
44000108	BITUMINOUS REMOVAL OVER PATCHES 2"	SQ YD	2446
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1531.36
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	281.77
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	437.53
48101200	AGGREGATE SHOULDERS, TYPE B	TON	424
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1470
70300220	TEMPORARY PAVEMENT MARKING -LINE 4"	FOOT	37192
70300280	TEMPORARY PAVEMENT MARKING -LINE 24"	FOOT	24
* 78000100	THERMOPLASTIC PAVEMENT MARKING -LETTERS & SYMBOLS	SQ FT	18
* 78000200	THERMOPLASTIC PAVEMENT MARKING -LINE 4"	FOOT	37192
* 78000650	THERMOPLASTIC PAVEMENT MARKING -LINE 24"	FOOT	24

SUMMARY OF QUANTITIES			TOTAL
CODE NO.	ITEM	UNIT	QUANTITIES <i>URBAN</i>
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	195
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	3063
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL. 4.75, N50	TON	1531.36

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: NONE  
DATE: FEB 10, 2004

DRAWN BY: T. FARMER  
CHECKED BY: