


SUMMARY OF QUANTITIES

CONTRACT 62829	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	305	2004-088B	COOK	145	5
	STA.	TO STA.			

CODE	ITEM DESCRIPTION	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE				X271-2A WILLOW RD. OVER MILWAUKEE AVE.	X071-2A WILLOW RD. OVER DES PLAINES RIVER	
				ROADWAY		SAFETY	BRIDGES			
				PCC PAVEMENT J000-2A			SFTY-3N			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	185	185						
20200100	EARTH EXCAVATION	CU YD	1,605	1,605						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	13	13						
20400800	FURNISHED EXCAVATION	CU YD	5,645	5,645						
20700220	POROUS GRANULAR EMBANKMENT	CU YD	521				451	70		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	13	13						
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	58	58						
20800150	TRENCH BACKFILL	CU YD	214	214						
20900110	POROUS GRANULAR BACKFILL	CU YD	22	22						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	4,191	4,191						
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,596	1,596						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	6,291	6,291						
25000210	SEEDING, CLASS 2A	ACRE	1	1						
25000312	SEEDING, CLASS 4A	ACRE	3	3						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	354	354						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	354	354						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	354	354						
25100630	EROSION CONTROL BLANKET	SO YD	38,044	38,044						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	393	393						
28000400	PERIMETER EROSION BARRIER	FOOT	3,907	3,907						
28000510	INLET FILTERS	EACH	40	40						
28100109	STONE RIPRAP, CLASS A5	SQ YD	430					430		
28500100	FABRIC FORMED CONCRETE REVETMENT MATS	SO YD	48	48						
31101810	SUB-BASE GRANULAR MATERIAL - TYPE B 12"	SO YD	4,191	4,191						
31200100	STABILIZED SUB-BASE 4"	SO YD	4,191	4,191						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6						
40600300	AGGREGATE (PRIME COAT)	TON	9	9						
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD	89	89						
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SO YD	2,380	2,380						
42001300	PROTECTIVE COAT	SO YD	6,789	6,789						
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO YD	1,162				566	596		
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SO YD	4,406	4,406						
44000100	PAVEMENT REMOVAL	SO YD	7,411	7,411						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,923	2,923						

▲ DENOTES SPECIALTY ITEM

		ILLINOIS DEPARTMENT OF TRANSPORTATION	
		SUMMARY OF QUANTITIES	
WILLow ROAD OVER US 45/IL 21 (MILWAUKEE AVE) AND OVER DES PLAINES RIVER		SCALE	DRAWN BY TCG
		DATE JANUARY 2005	CHECKED BY DES

P:\0000019\RoadAdvances Contract\11\AL500-rev1582071

01/12/2005 05:08:25 PM