CONTRACT 62829	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	305	2004-088B	COOK	145	6
	STA.		TO STA.		

SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE: ROADWAY: PCC PAVEMENT	ROADWAY	SAFETY		BRIDGES X271-2A: WILLOW RD. OVER MILWAUKEE AVE.	BRIDGES X071-2A: WILLOW RD. OVER DES PLAINES RIVER
				J000-2A		SFTY-3N			
44000700	APPROACH SLAB REMOVAL	SQ YD	840	840					
44001980	CONCRETE BARRIER REMOVAL	FOOT	2,160	2,160					
44003100	MEDIAN REMOVAL	SQ FT	702	702					
44004250	PAVED SHOULDER REMOVAL	SQ FT	1,723	1,723					
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	73	73					
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	618	618					
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	967	967					
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SQ YD	1,894	1,894					
48301000	PROTECTIVE COAT	SQ YD	1,894	1,894					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1					1	
50102400	CONCRETE REMOVAL	CU YD	31						31
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1						1
50200100	STRUCTURE EXCAVATION	CU YD	805					270	535
50200300	COFFERDAM EXCAVATION	CU YD	235						235
50200700	COFFERDAM (PIER 2)	EACH	2						2
50200800	COFFERDAM (PIER 3)	EACH	2						2
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	190						190
50300225	CONCRETE STRUCTURES	CU YD	653					263	390
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,288					544	744
50300260	BRIDGE DECK GROOVING	SQ YD	4,500					1,820	2,680
50300265	SEAL COAT CONCRETE	CU YD	135						135
50300300	PROTECTIVE COAT	SQ YD	6,080					2,230	3,850
50300440	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28						28
50300450	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28						28
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	129						129
50500305	ERECTING STRUCTURAL STEEL	L SUM	1					0.7	0.3
50500505	STUD SHEAR CONNECTORS	EACH	20,502					8,064	12,438
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	40						40
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	386,830					158,130	228,700
51100100	SLOPE WALL 4 INCH	SQ YD	720					720	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	5,430					3,544	1,886
51202700	DRIVING STEEL PILES	FOOT	5,430					3,544	1,886

△ DENOTES SPECIALTY ITEM

SQQ-2

Edwards AND Kelcey

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

WILLOW ROAD
OVER US 45/IL 21 (MILWAUKEE AVE)
AND OVER DES PLAINES RIVER

SCALE | DRAWN BY TCG
DATE JANUARY 2005 | CHECKED BY DES

P:\00001901A\cadd\Advance Contract\FINALSOQ-revised.dgn 04/12/2005 04:55:43 PM