

SUMMARY OF QUANTITIES

CONTRACT 62829	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	305	2004-088B	COOK	145	7
	STA.		TO STA.		

CODE	ITEM DESCRIPTION	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE				X271-2A	X031-2A	
				ROADWAY		SAFETY	BRIDGES			
				PCC PAVEMENT J000-2A			WILLOW RD. OVER MILWAUKEE AVE.			WILLOW RD. OVER DES PLAINES RIVER
51203600	TEST PILE STEEL HP12X53	EACH	7					3	4	
51205200	TEMPORARY SHEET PILING	SQ. FT.	1,100					1,100		
51500100	NAME PLATES	EACH	2					1	1	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3	3						
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2	2						
54215967	REINFORCED CONCRETE PIPE ELBOW 12"	EACH	12	12						
54247200	GRATING FOR CONCRETE FLARED END SECTION 54"	EACH	2	2						
Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	936	936						
55100400	STORM SEWER REMOVAL 10"	FOOT	386	386						
55100500	STORM SEWER REMOVAL 12"	FOOT	528	528						
55100900	STORM SEWER REMOVAL 18"	FOOT	38	38						
55101600	STORM SEWER REMOVAL 36"	FOOT	410	410						
58700200	BRIDGE SEAT SEALER	SQ FT	2,422					222	2,200	
59000100	EPOXY CRACK SEALING	FOOT	73						73	
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	144	144						
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2						
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	4	4						
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE A-24 FRAME AND GRATE	EACH	14	14						
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2						
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2						
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7						
60247160	DRAINAGE STRUCTURES, TYPE 1 WITH TWO TYPE 20 FRAMES AND GRATES	EACH	10	10						
60257700	MANHOLE ADJUSTING RING	EACH	42	42						
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	11	11						
60500040	REMOVING MANHOLES	EACH	2	2						
60500050	REMOVING CATCH BASINS	EACH	12	12						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	302	302						
60608509	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.18	FOOT	354	354						
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	96	96						
60624600	CORRUGATED MEDIAN	SQ FT	70	70						
Δ 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,771	1,771						
Δ 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3	3						
Δ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4						

Δ DENOTES SPECIALTY ITEM  
 Δ NON-PARTICIPATING

<b>Edwards AND Kelcey</b>	
REVISIONS	
NAME	DATE

S00-3

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

WILLOW ROAD  
OVER US 45/IL 21 (MILWAUKEE AVE)  
AND OVER DES PLAINES RIVER

SCALE \_\_\_\_\_ DRAWN BY TCG  
 DATE JANUARY 2005 CHECKED BY DES

P:\000003014\cadd\advance Contract\INAL500-rev\sbcd27