

## SUMMARY OF QUANTITIES

CONTRACT 62829	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	305	2004-088B	COOK	145	9
STA.	TO STA.				

CODE	ITEM DESCRIPTION	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				ROADWAY		SAFETY	BRIDGES	
				PCC PAVEMENT J000-2A			WILLOW RD. OVER MILWAUKEE AVE. X271-2A	WILLOW RD. OVER DES PLAINES RIVER X071-2A
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	793	793				
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	304	304				
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	329	329				
552A1600	STORM SEWERS JACKED IN PLACE, CLASS A 48"	FOOT	106	106				
X0320870	BRACED EXCAVATION	CU YD	260			260		
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	4				4	
X0323082	DRAINAGE SCUPPERS, DS-33	EACH	8			4	4	
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	40	40				
X0324159	WHITEWASHING FOR CONCRETE PAVEMENT	SO YD	4,191	4,191				
X0712400	TEMPORARY PAVEMENT	SO YD	356	356				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "D", N70	TON	461	461				
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	419	419				
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	2,968	2,968				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	180	180				
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 1	EACH	2				2	
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	2,214	2,214				
X0324112	BARRIER BASE	FOOT	2,126	2,126				
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	14	14				
XX002898	PIPE DRAINS, PERFORATED PVC, 8"	FOOT	35				35	
Z0001050	AGGREGATE SUBGRADE, 12"	SO YD	5,997	5,997				
Z0002600	BAR SPLICERS	EACH	2,972			1,309	1,663	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0030040	IMPACT ATTENUATORS (FULLY REDIRECTIVE, WIDE), TEST LEVEL 2	EACH	2		2			
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3		3			
Z0047300	PROTECTIVE SHIELD	SO YD	2,842			851	1,991	
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42" HEIGHT	FOOT	2,096	2,096				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	16	16				
70103800	TRAFFIC CONTROL SURVIELLANCE AND MAINTENANCE	CAL DA	220	220				
78300530	BARRIER WALL MARKERS, TYPE C	EACH	66	66				

▲ DENOTES SPECIALTY ITEM

<b>Edwards AND Kelcey</b>	
REVISIONS	DATE

S00-5

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

WILLOW ROAD  
OVER US 45/IL 21 (MILWAUKEE AVE)  
AND OVER DES PLAINES RIVER

SCALE \_\_\_\_\_ DRAWN BY TCG  
DATE JANUARY 2005 CHECKED BY DES

Rev.

P:\00001904\scada\advance Contract\VALS000-rev1\sed017