CONTRACT 62829

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2004-088B	COOK	145	16
STA.		TO STA.		

STORM SEWERS

PIPE NUMBER	STRUCTURE NUMBER	TO STR NO.	STORM SEWERS, CLASS A, TYPE 1 12" (FEET)	STORM SEWERS, CLASS A, TYPE 2 12" (FEET)	STORM SEWERS, CLASS A, TYPE 2 15" (FEET)	STORM SEWERS, CLASS A, TYPE 1 36" (FEET)	STORM SEWERS, CLASS A, TYPE 2 42" (FEET)	STORM SEWERS, CLASS A, TYPE 2 48" (FEET)	STORM SEWERS, CLASS A, TYPE 1 54" (FEET)	STORM SEWERS, CLASS A, TYPE 2 54" (FEET)	STORM SEWERS JACKED IN PLACE, CLASS A 48" (FOOT)	TRENCH BACKFILL (CU YD)
MILWAUKEE RAMP A												
A11	A11	B3					80					33.2
A12	A12	A13					284					
A13	A13	A11					314					
T1	EXIST.	PIPE	13									
T2	EXIST.	A12	7									
T3	T1	PIPE	3									
T4	T2	PIPE	7									
T5	EXIST.	PIPE	13									
T6	EXIST.	30	3									
MILWAUKEE RAMP B												
B1	B1	B3	4									
B2	B1	PLUG	7									
B3	B3	B8								329		
B4	PLUG	PIPE	8									
B6	PLUG	PIPE	8									
B8	B8	B9							52			
B9	B17	PIPE	18									
B10	B10	B11							47			
B11	B11	20									106	
B12	PLUG	PIPE	8									
B14	PLUG	PIPE	8									
B16	PLUG	30	8									
MILWAUKEE RAMP D												
D21	PLUG	24	14									
TOTAL			564	472	8	165	793	304	99	329	106	214

STORM SEWER REMOVALS, CLEANING, AND DRAINAGE STRUCTURE ADJUSTMENTS

SHEET	STATION	TO STATION	STORM SEWER REMOVAL 10" (FEET)	STORM SEWER REMOVAL 12" (FEET)	STORM SEWER REMOVAL 18" (FEET)	STORM SEWER REMOVAL 30" (FEET)	STORM SEWER REMOVAL 36" (FEET)	STORM SEWERS TO BE CLEANED (FEET)	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) (EACH)	REMOVING MANHOLES (EACH)	REMOVING CATCH BASINS (EACH)
D-1	384+90	395+00	288	459	38			936	1	2	8
D-2	395+00	402+80	98	69		0	410				4
D-5	19+09	23+58							10		
TOTAL			386	528	38	0	410	936	11	2	12

SCH-6

Edwards AND Kelcey

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

WILLOW ROAD
OVER US 45/IL 21 (MILWAUKEE AVE)
AND OVER DES PLAINES RIVER

SCALE

DRAWN BY CADD

DATE JANUARY 2005

CHECKED BY PJM

P:\00001904\cadd\Advance Contract\TIDRASCH.DGN 01/12/2005 02:52:38 PM