

F.A. RTE.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	0913.1	COOK	61	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
* FAP 305/ FAU 1285			CONTRACT# 62849	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN COOK CO. ROADWAY STATE 100% I000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	28	28				
21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	3038	3038				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	49	49				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	49	49				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	49	49				
25001820	SEEDING, CLASS 5 (MODIFIED)	ACRE	0.4	0.4				
25100630	EROSION CONTROL BLANKET	SQ YD	1758	1758				
25200110	SODDING, SALT TOLERANT	SQ YD	1280	1280				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1524	1524				
20200100	EARTH EXCAVATION	CU YD	2466	2466				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	69	69				
40600300	AGGREGATE (PRIME COAT)	TON	344	344				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	666.5	666.5				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2250	2250				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	475	475				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2220	2220				
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	114744	114744				
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	947	947				
44000106	BITUMINOUS REMOVAL OVER PATCHES 1 1/2"	SQ YD	5650	5650				
44000300	CURB REMOVAL	FOOT	7526	7526				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15016	15016				
44000600	SIDEWALK REMOVAL	SQ FT	2220	2220				
44001400	BITUMINOUS MEDIAN SURFACE REMOVAL	SQ YD	278	278				
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	42677	42677				
44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	6436	6436				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3700	3700				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN COOK CO. ROADWAY STATE 100% I000-2A				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	600	600				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1350	1350				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	200	200				
55039700	STORM SEWERS TO BE CLEANED	FOOT	1000	1000				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	14	14				
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	31	31				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60260100	INLETS TO BE ADJUSTED	EACH	13	13				
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	32	32				
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	32	32				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	160	160				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	12	12				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	150	150				
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	4739	4739				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	14400	14400				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	12178	12178				
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	13100	13100				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9				
67100100	MOBILIZATION	L SUM	1	1				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1				
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 305/ FAU 1285 (PALATINE ROAD)
CEDAR STREET TO EAST OF US 12

Rev.

12/17/2004 10:22:00 AM