

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAI 80	99-4-B-1-I	WILL	9	2

CONTRACT 62862

INDEX OF SHEETS

- 1 TITLE SHEET
- 2 INDEX OF SHEETS & GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 EAST SLOPE WALL DETAILS
- 5 WEST SLOPE WALL DETAILS
- 6 SLOPE WALL CROSS SECTION – (SECTION A-A)
- 7 RIP RAP CROSS SECTION – (SECTION B-B)
- 8 SLOPEWALL CROSS SECTION – (SECTION C-C)
- 9 TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURE, PARTIAL RAMP CLOSURE

STATE STANDARDS

- 701001-01 OFF ROAD OPERATIONS, 2L, 2W
- 701101-01 OFF ROAD OPERATIONS, MULTILANE
- 702001-05 TRAFFIC CONTROL DEVICES

GENERAL NOTES

- 1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- 2. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- 3. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS & CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION & ORDERING OF MATERIALS.
- 4. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE OR TOLLWAY PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- 5. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC SUPERVISOR AT (847) 705-4470 FOR ARTERIALS AND X-4151 or 4155 (FOR EXPRESSWAYS). A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
- 6. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM BRIDGE OFFICE INSPECTORS
- 7. SLOPE WALL SHALL BE REINFORCED WITH WELDED WIRE FABRIC, 6" X 6" – W 4.0 X W 4.0, WEIGHING 58 LBS PER 100 SQ. FT.
- 8. LAYOUT OF SLOPE PROTECTION SYSTEM MAY BE VARIED IN THE FIELD TO SUIT GROUND CONDITIONS AS DIRECTED BY THE ENGINEER.
- 9. SLOPE WALL REMOVAL SHALL BE DONE SUCH THAT A MINIMUM OF 1'-0" OF EXISTING REINFORCEMENT IS EXPOSED. THE EXISTING REINFORCEMENT SHALL BE LAPPED WITH THE NEW REINFORCEMENT AND INCORPORATED INTO THE NEW SLOPE WALL.

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS
GENERAL NOTES

Rev.