

SUMMARY OF QUANTITIES

80% F.E.D. / 20% STATE

F.A.P. RY. 305	SECTION 1313.1 B	COUNTY COOK	TOTAL SHEETS 193	SHEET NO. 5
----------------	------------------	-------------	------------------	-------------

CONTRACT NO. 62878

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE								50/50 LOCAL+STATE PARTICIPATION SFTY-IB
				ROADWAY J000-2A	ROADWAY I000-2A	BRIDGE (ELMHURST) X271-2A	RETAINING WALLS Y007	SIGNAL ELMHURST Y031-1F	SIGNS Y002-1C	LIGHTING Y030-1E		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	0	1	0	0	0	0	0	0
50200100	STRUCTURE EXCAVATION	CU YD	5652.8	0	0	5460.8	192	0	0	0	0	0
50300160	NEOPRENE EXPANSION JOINT 4"	FOOT	64	0	0	64	0	0	0	0	0	0
50300225	CONCRETE STRUCTURES	CU YD	1022.7	0	0	980.8	41.9	0	0	0	0	0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	717.5	0	0	717.5	0	0	0	0	0	0
50300260	BRIDGE DECK GROOVING	SQ YD	2118	0	0	2118	0	0	0	0	0	0
50300300	PROTECTIVE COAT	SQ YD	2720	0	0	2720	0	0	0	0	0	0
50300440	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20	0	0	20	0	0	0	0	0	0
50300450	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10	0	0	10	0	0	0	0	0	0
50500305	ERECTING STRUCTURAL STEEL	L SUM	1	0	0	1	0	0	0	0	0	0
50500505	STUD SHEAR CONNECTORS	EACH	10320	0	0	10320	0	0	0	0	0	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	308910	0	0	305770	3140	0	0	0	0	0
51205200	TEMPORARY SHEET PILING	SQ FT	2359	0	0	2359	0	0	0	0	0	0
51500100	NAME PLATES	EACH	1	0	0	1	0	0	0	0	0	0
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	738	0	738	0	0	0	0	0	0	0
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	158	0	158	0	0	0	0	0	0	0
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	90	0	90	0	0	0	0	0	0	0
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	19	0	19	0	0	0	0	0	0	0
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	426	0	426	0	0	0	0	0	0	0
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	264	0	264	0	0	0	0	0	0	0
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	292	0	292	0	0	0	0	0	0	0
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	528	0	528	0	0	0	0	0	0	0
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	87	0	87	0	0	0	0	0	0	0
55100400	STORM SEWER REMOVAL 10"	FOOT	461	0	461	0	0	0	0	0	0	0
55100500	STORM SEWER REMOVAL 12"	FOOT	135	0	135	0	0	0	0	0	0	0
55101400	STORM SEWER REMOVAL 30"	FOOT	136	0	136	0	0	0	0	0	0	0
55101600	STORM SEWER REMOVAL 36"	FOOT	768	0	768	0	0	0	0	0	0	0
58700200	BRIDGE SEAT SEALER	SQ FT	288	0	0	288	0	0	0	0	0	0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	157	0	0	157	0	0	0	0	0	0
60100905	PIPE DRAINS 4"	FOOT	23	0	0	23	0	0	0	0	0	0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD OVER IL 83 (ELMHURST RD.)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE 12/04

DRAWN BY ACE/CAD
CHECKED BY TAE



1378 palatine_04_01.rvt 12/22/04 03:07:05 PM