

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1313.1 B	COOK	193	8

CONTRACT NO. 62878

80% FED. / 20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	ROADWAY	BRIDGE (ELMHURST)	RETAINING WALLS	SIGNAL ELMHURST	SIGNS	LIGHTING	50/50 LOCAL:STATE PARTICIPATION SFTY-1B					
				J000-2A	I000-2A	X271-2A	Y007	Y031-IF	Y002-1C	Y030-1E						
				CONSTRUCTION TYPE CODE												
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	0	0	0	0	0	0	0	1	0				
80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	21	0	0	0	0	0	0	0	21	0				
80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	4	0	0	0	0	0	0	0	4	0				
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	508	0	0	0	0	508	0	0	0	0				
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	57	0	0	0	0	57	0	0	0	0				
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	334	0	0	0	0	65	0	269	0	0				
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	276	0	0	0	0	211	0	65	0	0				
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	85	0	0	0	0	85	0	0	0	0				
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	894	0	0	0	0	0	0	894	0	0				
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	394	0	0	0	0	394	0	0	0	0				
81022100	CONDUIT ENCASED IN CONCRETE, 2" DIA., PVC	FOOT	10	0	0	0	0	0	0	10	0	0				
81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	255	0	0	0	0	0	0	255	0	0				
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	8	0	0	0	0	0	0	0	8	0				
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	6	0	0	0	0	0	0	0	6	0				
81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	2	0	0	0	0	0	0	0	2	0				
81302620	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 21" X 11" X 6"	EACH	4	0	0	0	0	0	0	0	4	0				
81400100	HANDHOLE	EACH	8	0	0	0	0	0	8	0	0	0				
81400300	DOUBLE HANDHOLE	EACH	3	0	0	0	0	0	3	0	0	0				
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3820	0	0	0	0	752	0	3068	0	0				
81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	1650	0	0	0	0	0	0	1650	0	0				
81700375	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3/C NO. 4 AND 1/C NO. 6 GROUND	FOOT	50	0	0	0	0	0	0	50	0	0				
81701385	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 350MCM	FOOT	80	0	0	0	0	0	0	80	0	0				
81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	270	0	0	0	0	0	0	270	0	0				
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	5	0	0	0	0	0	0	5	0	0				
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	20	0	0	0	0	0	0	20	0	0				
82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8	0	0	0	0	0	0	8	0	0				
83000200	LIGHT POLE, ALUMINUM, 30 FT. M.H., 6 FT. DAVIT ARM	EACH	5	0	0	0	0	0	0	5	0	0				
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	180	0	0	0	0	0	0	180	0	0				
83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	5	0	0	0	0	0	0	5	0	0				
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	6	0	0	0	0	0	0	6	0	0				

© SFTY-3C
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD OVER IL 83 (ELMHURST RD.)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE 12/04

DRAWN BY ACE/CAD
CHECKED BY TAE



12/22/2004 03:07:26 PM