F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1313.1 B	COOK	193	88

CONTRACT NO. 62878

SIGNING SCHEDULE - GROUND MOUNTED SIGNS

			SIGN PANELS										TELESCOPING STEEL SIGN SUPPORT				WOOD SIGN SUPPORT				BREAKAWAY STEEL SIGN SUPPORT									
SIGN NO.	STATION	LT/RT	"AA" (L.F.)	"BB" (L.F.)	WIDTH (L.F.)	DEPTH (L.F.)	EXIST TO REMAIN (Y)	EXISTING SIGN TO BE RELOCATED (Y)	72000100 SIGN PANEL TYPE 1 (SQ. FT.)	72000200 SIGN PANEL TYPE 2 (SQ. FT.)	72000300 SIGN PANEL TYPE 3 (SQ. FT.)	72400330 REMOVE SIGN PANEL TYPE 3 (SQ. FT.)	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)	72800100 PAY LENGTH (L.F.)	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)	73000100 PAY LENGTH (L.F.)	POST SIZE	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)	P4 (L.F.)	813 PAY WEIGHT (LB.)	812A FND 2.0' DIA (L.F.)	812B FND 2.5' DIA (L.F.)	812C FND 3.0' DIA (L.F.)	816 FND REM (EACH)
NF-069TS	3361+00	LT	4.58	7.5	2.50	3.00			7.50				10.8	10.8		31.6														
NF-070TS	3362+74	RT	12.00	7.3	3.00	3.00			9.00				13.3	13.3		36.6														
NF-071TS					2.50	2.50			6.25																					
NF-072TS					1.50	2.00			3.00																					
NF-074SP	3363+00	LT			2.00	2.50			5.00																					
NF-075TS	3363+22	RT	5.30	7.4	2.00	2.00			4.00				10.3			15.3														
NF-076SP	3363+03	RT			5.50	1.00		Y																						
NF-077TS	3364+57	LT	8.56	7.0	2.00	2.00			4.00				11.2			16.2														
NF-078TS				0.0	1.75	1.25			2.19																					
NF-079TS					3.00	3.00			9.00																					
NF-080TS	3364+58	RT	4.50	7.4	3.00	3.00			9.00				10.8			15.8														
NF-081TS	3362+46	LT	4.58	7.6	2.00	2.00			4.00				10.3	10.3		30.6														
NF-181TS					1.50	2.00			3.00																					
NF-082SP	3364+36	RT			2.50	2.50			6.25																					
NF-083SP					2.00	2.00			4.00																					
NF-083ASP					2.00	2.50			5.00																					
NF-084TS	3362+18	RT	2.80	7.4	3.00	3.00			9.00				10.8	10.8		31.6														
NF-085TS	3366+00	LT	4.58	7.6	3.00	2.00			6.00				9.8			14.8														
NF-086TS	3366+00	RT	4.58	8.0	3.00	2.00			6.00				9.8			14.8														
NF-086ATS					1.00	1.50			1.50																					
SF-204TS	2361+69	LT	4.58	7.7	3.00	2.00			6.00				9.8			14.8														
SF-205TS	2361+69	RT	1.08	7.4	3.00	2.00			6.00				9.8			14.8														
SF-206TS	2361+69	RT			1.00	1.50			1.50																					
SF-207TS	2365+25	RT	9.50	7.3	2.00	2.00			4.00				10.3	10.3		30.6														
SF-107TS					1.50	2.00			3.00																					
SF-208TS	2365+37	LT	4.50	7.3	3.00	3.00			9.00				10.8			15.8														
SF-209TS	2362+95	LT	6.50	7.3	3.00	3.00			9.00				10.8			15.8														
SF-210TS	2362+85	RT	12.79	7.4	1.75	1.25			2.19				11.1			16.1														
SF-211TS					2.00	2.00			4.00																					
SF-212TS	2362+85	LT			3.00	3.00			9.00																					
SF-213SP	2363+20	LT			2.50	2.50			6.25																					
SF-214SP					2.00	2.00			4.00																					
SF-215SP					2.00	2.50			5.00																					
SF-216SP	2364+30	RT			2.00	2.50			5.00																					
SF-218SP	2367+34	LT			5.50	1.00		Y																						
SF-219TS	2364+49	LT	9.48	7.4	2.00	2.00			4.00				10.3			15.3														
SF-220TS	2364+80	LT	0.62	7.4	3.00	3.00			9.00				13.3	13.3		36.6														
SF-221TS					2.50	2.50			6.25																					
SF-222TS					1.50	2.00			3.00																					
83-330TS	745+50	LT	4.58	7.4	2.50	3.00			7.50				10.8	10.8		31.6														
83-331TS	747+09	LT	4.58	7.4	2.00	1.00			2.00				10.8			15.8														
83-332TS					2.00	2.00			4.00																					
83-333TS	748+10	RT	3.58	7.4	2.00	2.50			5.00				10.3			15.3														
83-334TS	752+45	RT	3.58	7.4	2.00	1.00			2.00				10.8			15.8														
83-335TS					2.00	2.00			4.00																					
83-336TS	754+00	RT	4.58	7.0	2.50	3.00			7.50				12.4	12.4		34.8														

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD OVER IL 83 (ELMHURST RD.)

GROUND MOUNTED SIGNS

SCALE: NONE
DATE 12/04

DRAWN BY ACE/CAD
CHECKED BY TAE

AMERICAN CONSULTING ENGINEERS