

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5	19B-2-D	STEPHENSON	57	3
STA. TO STA.			FED. AID PROJECT	
FED. ROAD DIST. NO.		ILLINOIS		

# SCHEDULE OF QUANTITIES

## 20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	UNITS
STA. 54+30 (RIGHT)	12
STA. 54+35 (RIGHT)	14
STA. 54+39 (RIGHT)	9
STA. 54+43 (RIGHT)	15
STA. 54+80 (RIGHT)	206
STA. 54+84 (RIGHT)	15
STA. 57+80 (RIGHT)	10
STA. 57+89 (RIGHT)	6
STA. 57+94 (RIGHT)	10
STA. 57+95 (RIGHT)	6
STA. 57+97 (RIGHT)	9
STA. 58+07 (RIGHT)	6
STA. 58+10 (RIGHT)	6
STA. 58+12 (RIGHT)	9
STA. 58+17 (RIGHT)	2012
STA. 58+20 (RIGHT)	7
TOTAL =	170

## 20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

LOCATION	UNITS
STA. 54+23 (RIGHT)	18
STA. 54+75 (RIGHT)	16
STA. 57+58 (RIGHT)	20
STA. 57+64 (RIGHT)	18
STA. 57+84 (RIGHT)	20
TOTAL =	92

## 20100500 TREE REMOVAL, ACRE

LOCATION	ACRE
STA. 55+40 (RIGHT)	0.25
TOTAL =	0.25

## 25001830 SEEDING, CLASS 6 (MODIFIED)

LOCATION	ACRE
STA. 54+00 TO 60+50 (LEFT)	1
STA. 54+00 TO 60+50 (RIGHT)	1
TOTAL =	2

## 28000300 TEMPORARY DITCH CHECKS

LOCATION	EACH
STA. 55+30 (RIGHT)	1
STA. 57+20 (RIGHT)	1
STA. 59+00 (RIGHT)	1
TOTAL =	3

## 28000400 PERIMETER EROSION BARRIER

LOCATION	FOOT
STA. 54+60.00 TO 55+36.00 (LEFT)	76
STA. 57+14.00 TO 60+35.00 (LEFT)	321
STA. 54+00.00 TO 55+36.00 (RIGHT)	136
STA. 57+14.00 TO 60+35.00 (RIGHT)	321
CONTRACTOR BORROW SITE	200
TOTAL =	1054

## 31100100 SUB-BASE GRANULAR MATERIAL, TYPE A

LOCATION	TON
STA. 57+50 TO 59+90 (UNDER PAVMT.) 12"	1026
STA. 57+50 TO 59+90 (UNDER SHLDRS.) 12"	454
STA. 54+38 TO 55+00	382
TOTAL =	1862

## 40600990 TEMPORARY RAMP

LOCATION	SQ. YD.
STA. 54+38.30 TO 54+43.30	42
STA. 59+85.00 TO 59+90.00	42
TOTAL =	84

## 42001165 BRIDGE APPROACH PAVEMENT

LOCATION	SQ. YD.
STA. 55+06 TO 55+36	223
STA. 57+14 TO 57+44	223
TOTAL =	446

## 42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)

LOCATION	SQ. YD.
STA. 54+38.30 TO 55+06	512
STA. 57+44 TO 57+50	46
TOTAL =	558

## 44000100 PAVEMENT REMOVAL

LOCATION	SQ. YD.
STA. 54+38.30 TO 55+36.00	724
STA. 57+14.00 TO 59+90.00	2065
TOTAL =	2789

## 48202400 BITUMINOUS SHOULDERS SUPERPAVE, 6" (INCLUDES GUARDRAIL WIDENING)

LOCATION	SQ. YD.
STA. 57+50.00 TO 59+90.00 (LEFT)	280
STA. 57+50.00 TO 59+90.00 (RIGHT)	280
TOTAL =	560

## 48202810 BITUMINOUS SHOULDERS SUPERPAVE, 10 1/2"

LOCATION	SQ. YD.
STA. 54+38 TO 55+06 (LT&RT)	159
TOTAL =	159

## 60602500 CONCRETE GUTTER, TYPE A

LOCATION	FT.
STA. 57+44 TO 60+57 (LEFT)	315
TOTAL =	315

## 63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

LOCATION	FT.
STA. 54+06.00 TO 55+06.00 (RIGHT) STAGE I	100.0
STA. 54+31.00 TO 55+06.00 (LEFT) STAGE II	75.0
STA. 57+44.00 TO 59+56.50 (LEFT) STAGE II	212.5
STA. 57+44.00 TO 59+94.00 (RIGHT) STAGE I	250.0
TOTAL =	637.5

## 63100085 TRAFFIC BARRIER TERMINAL, TYPE G

LOCATION	EACH
STA. 55+06.00 TO 55+36.00 (RIGHT) STAGE I	1
STA. 55+06.00 TO 55+36.00 (LEFT) STAGE II	1
STA. 57+14.00 TO 57+44.00 (RIGHT) STAGE I	1
STA. 57+14.00 TO 57+44.00 (LEFT) STAGE II	1
TOTAL =	4

## 63200305 STEEL PLATE BEAM GUARDRAIL REMOVAL

LOCATION	FT.
STA. 54+06.00 TO 55+36.00 (RIGHT) STAGE I	130.0
STA. 54+31.00 TO 55+36.00 (LEFT) STAGE II	105.0
STA. 57+14.00 TO 59+56.50 (LEFT) STAGE II	243.0
STA. 57+14.00 TO 59+94.00 (RIGHT) STAGE I	280.0
TOTAL =	758.0

## 63301990 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE J

LOCATION	EACH
STA. 59+56.50 TO 60+06.50 (LEFT)	1
TOTAL =	1

## 66101120 BITUMINOUS SHOULDER CURB

LOCATION	FT.
STA. 54+06 TO 55+07 (RIGHT)	101
TOTAL =	101

## 70300100 SHORT TERM PAVEMENT MARKING

LOCATION	FT.
STA. 54+38.3 TO 59+90 (RT LT) WHITE DASH	220
STA. 54+38.3 TO 59+90 YELLOW SOLID	1104
TOTAL =	1324

## 70300520 PAVEMENT MARKING TAPE, TYPE III 4"

LOCATION	FT.
(E) RT STA. 30+95 TO 63+05 WHITE EDGE	3210
(W) LT STA. 47+10 TO 64+00 WHITE EDGE	1690
(E & W) STA. 37+54 TO 80+15 YELLOW	8522

## STAGE II

LOCATION	FT.
(E & W) STA. 37+66 TO 78+18 YELLOW	8104
(E) RT STA. 50+76 TO 63+50 WHITE EDGE	1274
(W) LT STA. 50+63 TO 84+78 WHITE EDGE	3415
TOTAL =	26215

## 70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	SQ. FT.
SEE SHORT TERM PAVEMENT MARKING SCHEDULE	221
SEE PAVEMENT MARKING TAPE TYPE III, 4" SCHEDULE	8739
TOTAL =	8960

## 70400100 TEMPORARY CONCRETE BARRIER

LOCATION	FT.
STA. 52+24 TO 61+07 (LEFT & RIGHT) STAGE I	890
STA. 52+76 TO 63+33 (LEFT & RIGHT) STAGE II	170
TOTAL =	1060

## 70400200 RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FT.
STA. 52+76 TO 61+58 (LEFT & RIGHT)	890
TOTAL =	890

## 78001110 PAINT PAVEMENT MARKING LINE 4"

LOCATION	FT.
STA. 30+51 TO 79+93 (RIGHT) WHITE DASH	1236
STA. 50+08 TO 63+05 (RIGHT) WHITE EDGE	1297
STA. 40+91 TO 74+53 (RIGHT) DOUBLE YELLOW	6724
STA. 40+91 TO 74+53 (LEFT) DOUBLE YELLOW	6724
STA. 38+42 TO 85+33 (LEFT) WHITE DASH	1173
STA. 47+21 TO 64+00 (LEFT) WHITE EDGE	1679
TOTAL =	18833

## 78100100 RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	EACH
STA. 54+38 TO 59+90 (LT), WHITE	7
STA. 54+38 TO 59+90 (RT), WHITE	7
STA. 54+38 TO 59+90 (RT), YELLOW	14
STA. 54+38 TO 59+90 (LT), YELLOW	14
TOTAL =	42

## 78200410 GUARDRAIL MARKERS, TYPE A

LOCATION	EACH
STA. 54+06 (RIGHT)	1
STA. 54+61 (RIGHT)	1
STA. 55+16 (RIGHT)	1
STA. 54+31 (LEFT)	1
STA. 54+86 (LEFT)	1
STA. 57+14 (LEFT/RIGHT)	2
STA. 57+69 (LEFT/RIGHT)	2
STA. 58+24 (LEFT/RIGHT)	2
STA. 58+79 (LEFT/RIGHT)	2
STA. 59+34 (LEFT/RIGHT)	2
STA. 59+89 (LEFT/RIGHT)	2
TOTAL =	17

## 78201000 TERMINAL MARKER DIRECT APPLIED

LOCATION	EACH
STA. 60+06.50 (LEFT)	1
TOTAL =	1

## 78300100 PAVEMENT MARKING REMOVAL

LOCATION	SQ. FT.
STA. 30+51.00 TO 40+91.00 (RT) STAGE I, WHITE DASH	87
STA. 38+42.39 TO 76+55.00 (LT) STAGE I, WHITE DASH	318
STA. 40+91.00 TO 53+86.00 (RT) STAGE I, DOUBLE YELLOW	863
STA. 40+91.00 TO 53+86.00 (LT) STAGE I, DOUBLE YELLOW	863
STA. 47+20.90 TO 64+00.00 (LT) STAGE I, WHITE EDGE	759
STA. 60+35.00 TO 74+53.00 (RT) STAGE I, DOUBLE YELLOW	945
STA. 60+35.00 TO 74+53.00 (LT) STAGE I, DOUBLE YELLOW	945
STA. 40+91.00 TO 79+93.00 (RT) STAGE II, WHITE DASH	325
STA. 50+08.00 TO 63+05.00 (RT) STAGE II, WHITE EDGE	432
STA. 76+55.00 TO 85+33.00 (LT) STAGE II, WHITE DASH	74
TOTAL =	5611

## 78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
STA. 54+38 TO 59+90 (LT), WHITE	7
STA. 54+38 TO 59+90 (RT), WHITE	7
STA. 54+38 TO 59+90 (RT), YELLOW	14
STA. 54+38 TO 59+90 (LT), YELLOW	14
TOTAL =	42

## X4066414 BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX, C, N50

LOCATION	TONS
STA. 54+38 TO 55+06	18
STA. 57+50 TO 59+90 (LEFT)	30
STA. 57+50 TO 59+90 (RIGHT)	26
TOTAL =	74

## X4066426 BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX, D, N70

LOCATION	TONS
STA. 54+38 TO 55+06	44
STA. 57+50 TO 59+90 (LEFT & RIGHT)	156
TOTAL =	200

## X4066616 BIT. CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70

LOCATION	TONS
STA. 54+38.00 TO 55+06.00	231
STA. 57+50.00 TO 59+90.00 (LEFT & RIGHT)	816
TOTAL =	1047

## Z0030250 IMPACT ATTENUATOR (TEMPORARY) NON-REDIRECTIVE TEST LEVEL 3

LOCATION	EACH
STAGE I	2
TOTAL =	2

## Z0030350 IMPACT ATTENUATOR (RELOCATE) NON-REDIRECTIVE TEST LEVEL 3

LOCATION	EACH
STAGE II	2
TOTAL =	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.  
DATE 5-20-03 DRAWN BY DH  
CHECKED BY SK

\* Cost of removing existing bridge rails included with "Removal of Existing Concrete Deck".