

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WINNEBAGO	317	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY 1000-2A
20100500	TREE REMOVAL, ACRES	ACRE	1
20200100	EARTH EXCAVATION	CU YD	5,965
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	237
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	2,390
20400800	FURNISHED EXCAVATION	CU YD	2,735
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,798
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	14,396
21101620	TOPSOIL FURNISH AND PLACE, 5"	SQ YD	37,406
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	24,546
21400100	GRADING AND SHAPING DITCHES	FOOT	75
25000210	SEEDING, CLASS 2A	ACRE	20
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,785
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,785
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,785
25100630	EROSION CONTROL BLANKET	SQ YD	95,977
28000300	TEMPORARY DITCH CHECKS	EACH	2
28000400	PERIMETER EROSION BARRIER	FOOT	29,022
28000500	INLET AND PIPE PROTECTION	EACH	11
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	89
28300400	AGGREGATE DITCH	TON	61
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	3,244
35100100	AGGREGATE BASE COURSE, TYPE A	TON	336
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	157.2
40600300	AGGREGATE (PRIME COAT)	TON	469
40600895	CONSTRUCTING TEST STRIP	EACH	3
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	6,828
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2,800
40600990	TEMPORARY RAMP	SQ YD	5,450
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	100
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	210
42001200	PAVEMENT FABRIC	SQ YD	1,626
44000100	PAVEMENT REMOVAL	SQ YD	4,023
44000113	BITUMINOUS REMOVAL OVER PATCHES 3 1/4"	SQ YD	539
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	745
44001300	BITUMINOUS CONCRETE SURFACE REMOVAL (SPECIAL)	SQ YD	3,616
44004000	PAVED DITCH REMOVAL	FOOT	55

* SPECIALTY ITEMS

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY 1000-2A
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,330
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	1,755
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	514
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	1,519
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	377
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	188
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	1,474
44213000	PATCHING REINFORCEMENT	SQ YD	3,918
44213200	SAW CUTS	FOOT	23,036
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	11,472
48100100	AGGREGATE SHOULDERS, TYPE A	TON	1,699
48202100	BITUMINOUS SHOULDERS SUPERPAVE 3"	SQ YD	11,620
48202205	BITUMINOUS SHOULDERS SUPERPAVE 4 1/4"	SQ YD	6,021
48202215	BITUMINOUS SHOULDERS SUPERPAVE 4 3/4"	SQ YD	395
50104400	CONCRETE HEADWALL REMOVAL	EACH	6
50105220	PIPE CULVERT REMOVAL	FOOT	452
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	164
50300155	NEOPRENE EXPANSION JOINT 2 1/2"	FOOT	164
50300225	CONCRETE STRUCTURES	CU YD	16.7
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,470
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	537
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	534
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	50
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	8
54215970	REINFORCED CONCRETE PIPE ELBOW 15"	EACH	6
54215979	REINFORCED CONCRETE PIPE ELBOW 24"	EACH	1
54245205	INLET BOX, STANDARD 542511	EACH	1
54246205	INLET BOX, STANDARD 542526	EACH	3
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	5
60107600	PIPE UNDERDRAINS 4"	FOOT	1,710
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	155
60224500	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60260100	INLETS TO BE ADJUSTED	EACH	5
60500060	REMOVING INLETS	EACH	3
60600705	CONCRETE CURB, TYPE B (ABUTTING EXISTING PAVEMENT)	FOOT	1,018

Δ SFTY-2A
 * SPECIALTY ITEMS

PLT DATE = Thu Jun 06 14:27:35 2002
 PLOT SCALE = 50.0000' / IN.
 REFERENCE = #REF*