

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WINNEBAGO	317	28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION	MAINLINE	
1	2433 + 09	RIGHT	
1	2434 + 35	LEFT	
1	2465 + 57	RIGHT	
1	2465 + 77	LEFT	
1	2470 + 43	LEFT	
1	2470 + 68	RIGHT	
1	2549 + 39	LEFT	
1	2551 + 04	RIGHT	
1	2557 + 27	LEFT	
1	2557 + 89	RIGHT	
1	2569 + 52	LEFT	
1	2569 + 65	RIGHT	
1	2571 + 85	MEDIAN	
1	2572 + 41	MEDIAN	
1	2584 + 21	MEDIAN	
1	2584 + 59	MEDIAN	
1	2605 + 69	MEDIAN	
1	2606 + 33	MEDIAN	
1	2607 + 66	MEDIAN	
1	2609 + 59	MEDIAN	
1	2633 + 81	MEDIAN	
1	2635 + 45	MEDIAN	
1	2637 + 15	RIGHT	
1	2643 + 30	RIGHT	
1	2653 + 14	LEFT	
1	2655 + 41	LEFT	
1	2661 + 31	RIGHT	
1	2665 + 39	MEDIAN	
1	2665 + 78	MEDIAN	
1	2669 + 78	LEFT	
1	2670 + 64	MEDIAN	
1	2672 + 57	MEDIAN	
1	2676 + 63	RIGHT	
1	2679 + 19	RIGHT	
1	2689 + 55	RIGHT	
1	2689 + 90	LEFT	
1	2693 + 13	MEDIAN	
1	2695 + 26	MEDIAN	
1	2708 + 50	RIGHT	
1	2709 + 76	MEDIAN	
1	2711 + 45	MEDIAN	
1	2719 + 19	RIGHT	
1	2721 + 21	RIGHT	
1	2728 + 39	LEFT	
1	2729 + 44	RIGHT	
1	2735 + 53	MEDIAN	
1	2736 + 11	RIGHT	
1	2737 + 66	MEDIAN	
1	2738 + 46	LEFT	
1	2742 + 57	RIGHT	
	RAMP AD		
1	62 + 00	RIGHT	
	RAMP BD		
1	43 + 49	LEFT	
1	45 + 70	RIGHT	
1	63 + 71	LEFT	
1	64 + 00	RIGHT	
	RAMP DB		
1	45 + 21	LEFT	
1	45 + 50	RIGHT	
TOTAL	57		

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
400.0	I-39 NORTHBOUND 2540 + 00 TO 2546 + 00
300.0	RAMP AD 84 + 00 TO 90 + 00
1,439.7	US 20 EASTBOUND 2649 + 50 TO 2671 + 00
TOTAL	2,139.7

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
850	2430 + 44 TO 2745 + 33 VARIOUS LOCATIONS
TOTAL	850

Z0001700 APPROACH SLAB REPAIR (FULL DEPTH)

SQ YD	LOCATION
13.33	I-39 NORTHBOUND 2469 + 50 10' LEFT LANE
8.00	2551 + 30 6' LEFT LANE
66.67	2554 + 50 25' RIGHT & LEFT LANES
6.67	2555 + 13 5' RIGHT LANE
13.33	2558 + 45 5' RIGHT & LEFT LANES
6.67	2561 + 30 5' RIGHT LANE
TOTAL	114.7

Z0028415 GEOTECHNICAL REINFORCEMENT

SQ YD	LOCATION
265.70	5% OF CLASS A PATCHING AREAS
27.60	5% OF CLASS B PATCHING AREAS
30.60	5% OF PARTIAL DEPTH PATCHING AREAS
TOTAL	323.90

Z0028700 GRANULAR SUBGRADE REPLACEMENT

CU YD	LOCATION	
58.77	5% OF CLASS A PATCHING AREAS	MAINLINE=1280 SQYD
9.20	5% OF CLASS B PATCHING AREAS	
10.18	5% OF PARTIAL DEPTH PATCHING AREAS	
TOTAL	78.15	

Z0030030 IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

EACH	LOCATION
1	2571 + 85 MEDIAN
1	2572 + 41 MEDIAN
1	2584 + 21 MEDIAN
1	2584 + 59 MEDIAN
1	2605 + 33 MEDIAN
1	2605 + 69 MEDIAN
1	2607 + 66 MEDIAN
1	2609 + 59 MEDIAN
1	2633 + 81 MEDIAN
1	2635 + 45 MEDIAN
1	2665 + 39 MEDIAN
1	2665 + 78 MEDIAN
1	2670 + 64 MEDIAN
1	2672 + 57 MEDIAN
1	2693 + 13 MEDIAN
1	2695 + 26 MEDIAN
1	2709 + 76 MEDIAN
1	2711 + 45 MEDIAN
1	2735 + 53 MEDIAN
1	2737 + 66 MEDIAN
TOTAL	20

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
1	2652 + 25 STAGE I
TOTAL	1

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
2	2659 + 54 STAGE 3 & 4
TOTAL	2

Z0056220 SAND MODULE IMPACT ATTENUATOR TO BE REMOVED

EACH	LOCATION
14	2738 + 70 TO 2739 + 20 MEDIAN
TOTAL	14

PLOT DATE = Fri, Jan 07, 07:35:40, 2005
 FILE NAME = c:\pwork\11212500\11212500.dgn
 PLOT SCALE = 50.00000 / IN.
 REFERENCE = #REF#