BITUMINOUS SCHEDULE

STATION	REMARKS	LENGTH	PROPOSED SURFACE		BIT SHOULDERS SUPERPAVE, 3" *				BIT SHOULDERS SUPERPAVE, 4 1/4" *				BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50				TOPSOIL FURNISH AND PLACE, 4", 5" OR 6"							
					INSIDE or LEFT		OUTSIDE or RIGHT		INSIDE or LEFT		OUTSIDE or RIGHT		INSIDE or LEFT		OUTSIDE or RIGHT		INSIDE OR LEFT				OUTSIDE OR RIGHT			
		(FT)	WIDTH (FT)	AREA (SQ YDS)	WIDTH (FT)	SQ YD	WIDTH (FT)	SQ YD	WIDTH (FT)	SQ YD	WIDTH (FT)	SQ YD	WIDTH (FT)	TON	WIDTH (FT)	TON	WIDTH (FT)	4" - SQ YD	5" - SQ YD	6" - SQ YD	WIDTH (FT)	4" - SQ YD	5" - SQ YD	6" - SQ YD
2670+04.34 - 2681+05	3 3/4" RESURFACING	1100.7	24	2,935									4	102.7	10	256.8	4.5		550.3		4.5		550.3	
2681+05 - 2682+55	TAPER & BUTT JOINT, 3 3/4" - 1 1/4"	150.0	24	400									4	14.0	10	35.0	4.5		75.0		4.5		75.0	
2682+55 - 2683+55	Bridge Approach Pavement	100.0																						
2683+55 - 2686+32	BRIDGE OMISSION, SN 101-0070, C&CI RR	277.0																						
2686+32 - 2687+32	Bridge Departure Pavement	100.0																						
2687+32 - 2688+82	BUTT JOINT & TAPER, 1 1/4" - 3 3/4"	150.0	24	400									4	14.0	VAR	38.5	4.5		75.0		4.5		75.0	
2688+82 - 2706+35	3 3/4" RESURFACING	1753.0	24	4,675									4	163.6	10	409.0	4.5		876.5		4.5		876.5	
2706+35 - 2708+38	US 20 EB OFF RAMP	202.5	VAR	664									4	18.9	10	47.3	4.5		101.3		4.5		101.3	
2708+38 - 2709+88	MILL 0" - 3 1/4" & BIT TAPER, 3 3/4" - 3 1/4"	150.0	VAR	650									4	12.1	10	30.3	4.5		75.0		4.5		75.0	
2709+88 - 2711+94	MILL 3 1/4" & RESURFACE 3 1/4"	206.0	VAR	1,110									4	16.7	10	41.7	4.5		103.0		4.5		103.0	
2711+94 - 2712+94	MILL 3 1/4" - 0" & BIT TAPER 3 1/4" - 3 1/2"	100.0	40	444									4	8.1	VAR	27.3	4.5		50.0		4.5		50.0	
2712+94 - 2713+44	TAPER, 3 1/2" - 3 3/4"	50.0	24	133									4	4.7	10	11.7	4.5		25.0		4.5		25.0	
2713+44 - 2720+84		740.0	24	1,973									4	69.1	10	172.7	4.5		370.0		4.5		370.0	
2720+84 - 2722+03	TAPER, 3 3/4" - 1 3/4"	119.5	24	319									4	11.2	VAR	20.9	4.5		59.8		4.5		59.8	
2722+03 - 2722+34	TAPER & BUTT JOINT, 1 3/4" - 1 1/4"	30.5	24	81									4	2.8			4.5		15.3		4.5		15.3	
2722+34 - 2723+34	Bridge Approach Pavement	100.0																						
2723+34 - 2725+57	BRIDGE OMISSION, SN 101-0071, Harrison Ave	223.0																						
2725+57 - 2726+57	Bridge Departure Pavement	100.0																						
2726+57 - 2728+07	BUTT JOINT & TAPER, 1 1/4" - 3 3/4"	150.0	40	667									4	14.0	10	35.0	4.5		75.0		4.5		75.0	
2728+07 - 2729+00		93.5	24	249									4	8.7	VAR	32.7	4.5		46.8		4.5		46.8	
2729+00 - 2734+02		502.0	24	1,339									4	46.9	VAR	205.0	4.5		251.0		4.5		251.0	
2734+02 - 2735+26		124.0	VAR	592									4	11.6	10	28.9	4.5		62.0		4.5		62.0	
2735+26 - 2736+06	MILL 0" - 3 1/4" & TAPER, 3 3/4" - 3 1/4"	80.0	40	356									4	6.5	10	16.2	4.5		40.0		4.5		40.0	
2736+06 - 2739+80	MILL 3 1/4" & RESURFACE 3 1/4"	374.0	36	1,496									4	30.3	10	75.6	4.5		187.0		4.5		187.0	
2739+80 - 2740+03	gap in crossover	23.0	36	92									10	5.4	10	5.4	4.5		11.5		4.5		11.5	
2740+03 - 2744+04	Barrier Wall on Left	401.0	36	1,604									8	74.9	10	93.6	4.5		200.5		4.5		200.5	
2744+04 2745+33.63	TAPER & BUTT JOINT, 3 1/4" - 1 1/4"	129.6	VAR	547									8	24.2	10	30.2	4.5		64.8		4.5		64.8	
2745+33.63	PROJECT ENDS @ TOLLWAY STA 2745+33.63																							
	EASTBOUND TOTALS	18,759.9		52,284.4						379.7		1,081.0		1,660.2		4,047.9			9,007.8				9,251.1	

STATION	REMARKS	LENGTH	PROPOSED SURFACE		48100100 6" & VAR. AGG SHLD TYPE A	40600200 BIT. PRIME	40600300 AGG PRIME	21001000 GEO. FABRIC FOR GRD. STAB.	31100100 15" SUB-BASE GRAN MAT TYPE A	X4073116 BIT CONC PVT (FD), SUP, 11 3/4"	X4066750 LEVEL BIND (HM) SUP, N105	#2001298 POLY BIT CONC BIND CSE SUP IL-9.5 N105	X4066660 POLY BIT CONC BIND CSE SUP IL-19.0 N105	X4066540 POLY BIT CONC SC SUPERPAVE MIX "E" N105	70300220 TEMP PAV'T MARKING - LINE 4"	
															(WHITE CENTERLINE)	(WHITE EDGE LINE)
		(FT)	WIDTH (FT)	AREA (SQ YDS)	TON	TON	TON	SQ YD	TON	SQ YD	TON	TON	TON	TON	FOOT	FOOT
2670+04.34 - 2681+05	3 3/4" RESURFACING	1100.7	24	2,935		1.994	7.00				1.14		369.8	246.5	440.3	176.1
2681+05 - 2682+55	TAPER & BUTT JOINT, 3 3/4" - 1 1/4"	150.0	24	400		0.272	1.00				0.16		50.4	33.6	60.0	24.0
2682+55 - 2683+55	Bridge Approach Pavement	100.0														
2683+55 - 2686+32	BRIDGE OMISSION, SN 101-0070, C&CI RR	277.0														
2686+32 - 2687+32	Bridge Departure Pavement	100.0														
2687+32 - 2688+82	BUTT JOINT & TAPER, 1 1/4" - 3 3/4"	150.0	24	400		0.279	1.00				0.16		50.4	33.6	60.0	24.0
2688+82 - 2706+35	3 3/4" RESURFACING	1753.0	24	4,675		3.175	11.20				1.82		589.0	392.7	701.2	280.5
2706+35 - 2708+38	US 20 EB OFF RAMP	202.5	VAR	664		0.420	1.50				0.21		83.6	55.8	81.0	32.4
2708+38 - 2709+88	MILL 0" - 3 1/4" & BIT TAPER, 3 3/4" - 3 1/4"	150.0	VAR	650		0.379	1.40				0.16		63.7	54.6	60.0	24.0
2709+88 - 2711+94	MILL 3 1/4" & RESURFACE 3 1/4"	206.0	VAR	1,110		0.614	2.20				0.21		108.8	93.2	82.4	33.0
2711+94 - 2712+94	MILL 3 1/4" - 0" & BIT TAPER 3 1/4" - 3 1/2"	100.0	40	444		0.274	1.00				0.10		43.6	37.3	40.0	16.0
2712+94 - 2713+44	TAPER, 3 1/2" - 3 3/4"	50.0	24	133		0.091	0.40				0.05		16.8	11.2	20.0	8.0
2713+44 - 2720+84		740.0	24	1,973		1.340	4.70				0.77		248.6	165.8	296.0	118.4
2720+84 - 2722+03	TAPER, 3 3/4" - 1 3/4"	119.5	24	319		0.202	0.60				0.12		40.2	26.8	47.8	19.1
2722+03 - 2722+34	TAPER & BUTT JOINT, 1 3/4" - 1 1/4"	30.5	24	81		0.041	0.20				0.03		10.2	6.8	12.2	4.9
2722+34 - 2723+34	Bridge Approach Pavement	100.0														
2723+34 - 2725+57	BRIDGE OMISSION, SN 101-0071, Harrison Ave	223.0														
2725+57 - 2726+57	Bridge Departure Pavement	100.0														
2726+57 - 2728+07	BUTT JOINT & TAPER, 1 1/4" - 3 3/4"	150.0	40	667		0.386	1.40				0.16		84.0	56.0	60.0	24.0
2728+07 - 2729+00		93.5	24	249		0.192	0.70				0.10		31.4	20.9	37.4	15.0
2729+00 - 2734+02		502.0	24	1,339		1.089	3.90				0.52		168.7	112.4	200.8	80.3
2734+02 - 2735+26		124.0	VAR	592		0.337	1.20				0.13		74.6	49.8	49.6	19.8
2735+26 - 2736+06	MILL 0" - 3 1/4" & TAPER, 3 3/4" - 3 1/4"	80.0	40	356		0.206	0.80				0.08		34.8	29.9	32.0	12.8
2736+06 - 2739+80	MILL 3 1/4" & RESURFACE 3 1/4"	374.0	36	1,496		0.891	3.20				0.39		146.6	125.7	149.6	59.8
2739+80 - 2740+03	gap in crossover	23.0	36	92		0.061	0.30				0.02		11.6	7.7	9.2	3.7
2740+03 - 2744+04	Barrier Wall on Left	401.0	36	1,604		1.032	3.70				0.42		202.1	134.7	160.4	64.2
2744+04 2745+33.63	TAPER & BUTT JOINT, 3 1/4" - 1 1/4"	129.6	VAR	547		0.346	1.30				0.13		69.0	46.0	51.9	20.7
2745+33.63	PROJECT ENDS @ TOLLWAY STA 2745+33.63															
	EASTBOUND TOTALS	18,759.9		52,284.4		34.28	127.62	3,797.38	3,243.59	2,278.43	17.26		6368.8	4391.9	6998.4	2799.3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Thu Dec 23 14:38:42 2004
FILE NAME = C:\projects\b21250B\d125b2cv.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = $$$$$$