

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WINNEBAGO	317	39
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# BITUMINOUS SCHEDULE

STATION MISCELLANEOUS	REMARKS	LENGTH (FT)	PROPOSED SURFACE		BIT SHOULDERS SUPERPAVE, 3" **				BIT SHOULDERS SUPERPAVE, 4 1/4" **				BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50				TOPSOIL FURNISH AND PLACE, 4", 5" OR 6"																				
			WIDTH (FT)	AREA (SQ YDS)	INSIDE or LEFT		OUTSIDE or RIGHT		INSIDE or LEFT		OUTSIDE or RIGHT		INSIDE or LEFT		OUTSIDE or RIGHT		INSIDE OR LEFT				OUTSIDE OR RIGHT																
					WIDTH (FT)	SQ YD	WIDTH (FT)	SQ YD	WIDTH (FT)	SQ YD	WIDTH (FT)	SQ YD	WIDTH (FT)	TON	WIDTH (FT)	TON	WIDTH (FT)	4" - SQ YD	5" - SQ YD	6" - SQ YD	WIDTH (FT)	4" - SQ YD	5" - SQ YD	6" - SQ YD													
2440+32 - 2445+68	MEDIAN CROSS-OVER CONCRETE CROSSOVER	535.0		2869.9														4.5			267.5																
			On-Ramp, EB Harrison to WB 20																																		
2710+30 - 2710 + 78		48.0	16.0	85	VAR	1.8	8.0	7.2										VAR	3.0	8	11.9	4.5				24.0				4.5				24.0			
2710+78 - 2712 + 28	TAPER & BUTT JOINT, 3 3/4" - 1 1/4"	150.0	16.0	267		4.0	11.2	8.0	22.4									4.0	18.7	8	37.3	4.5				75.0				4.5				75.0			
			OFF-Ramp, EB 20 to EB 20																																		
2711+94 - 2713 + 44	TAPER & BUTT JOINT, 3 1/4" - 1 1/4"	150.0	16.0	267		4.0	11.2	10.0	28.0									4.0	18.7	10	46.7	4.5				75.0				4.5				75.0			
			OFF-Ramp, WB 20 to EB 20																																		
2718+24 - 2719 + 74	BUTT JOINT & TAPER, 1 1/4" - 3 3/4"	150.0	16.0	267		4.0	11.2	8.0	22.4									4.0	18.7	8	37.3	4.5				75.0				4.5				75.0			
2719+74 - 2721 + 00		126.0	16.0	224		0.0	0.0	8.0	18.8											8	31.4	4.5				63.0				4.5				63.0			
			On-Ramp, EB Harrison to EB 20																																		
2721+42 - 2722 + 00	BUTT JOINT	60.0	16.0	107		4.0	4.5	10.0	11.2									4.0	7.5	10	18.7	4.5				30.0				4.5				30.0			
			OFF-Ramp, EB 20 to WB Harrison																																		
2727+72 - 2728 + 18		46.0	16.0	82				10.0	8.6												10	14.3	4.5				23.0				4.5				23.0		
2728+18 - 2729 + 68	TAPER & BUTT JOINT, 3 3/4" - 1 1/4"	150.0	16.0	267				10.0	28.0												10	46.7	4.5				75.0				4.5				75.0		
			On-Ramp, WB 20 TO NB 39																																		
2733+18 - 2734 + 00	BUTT JOINT	88.0	16.0	156		4.0	6.6	10.0	16.4									8.0	21.9	10.0	27.4	4.5				44.0				4.5				44.0			
			On-Ramp DA to WB 20																																		
2573+40 - 2574 + 90	3 3/4" - 1 1/4", BIT BUTT JOINT	150.0	16.0	267				6.0	16.8												6.0	28.0	4.5				75.0				4.5				75.0		
			MISCELLANEOUS AREA TOTALS																																		
			COLUMN TOTALS																																		
			PAY ITEM TOTALS																																		

STATION MISCELLANEOUS	REMARKS	LENGTH (FT)	PROPOSED SURFACE		48100100	40600200	40600300	21001000	31100100	X4073116	X4066750	#2001298	X4066660	X4066540	70300220	TEMP PAVT MARKING - LINE 4"	
			WIDTH (FT)	AREA (SQ YDS)	6" & VAR. AGG SHLD TYPE A	BIT. PRIME	AGG PRIME	GEO. FABRIC FOR GRD. STAB.	15" SUB-BASE GRAN MAT TYPE A	BIT CONC PVT (FD), SUP, 11 3/4"	LEVEL BIND (HM) SUP, N105	POLY BIT CONC BIND CSE SUP IL-9.5 N105	POLY BIT CONC BIND CSE SUP IL-19.0 N105	POLY BIT CONC SC SUPERPAVE MIX "E" N105	(WHITE CENTERLINE)	(WHITE EDGE LINE)	
					TON	TON	TON	SQ YD	TON	TON	TON	TON	TON	TON	TON	FOOT	FOOT
2440+32 - 2445+68	MEDIAN CROSS-OVER CONCRETE CROSSOVER	535.0		2869.9	40.6	1.642	4.40										
			On-Ramp, EB Harrison to WB 20														
2710+30 - 2710 + 78		48.0	16.0	85		0.059	0.20			0.10			10.8	7.2	19.2	7.7	
2710+78 - 2712 + 28	TAPER & BUTT JOINT, 3 3/4" - 1 1/4"	150.0	16.0	267		0.200	0.40			0.31			33.6	22.4	60.0	24.0	
			OFF-Ramp, EB 20 to EB 20														
2711+94 - 2713 + 44	TAPER & BUTT JOINT, 3 1/4" - 1 1/4"	150.0	16.0	267		0.215	0.40			0.31			33.6	22.4	60.0	24.0	
			OFF-Ramp, WB 20 to EB 20														
2718+24 - 2719 + 74	BUTT JOINT & TAPER, 1 1/4" - 3 3/4"	150.0	16.0	267		0.200	0.40			0.31			33.6	22.4	60.0	24.0	
2719+74 - 2721 + 00		126.0	16.0	224		0.144	0.40			0.26			28.2	18.8	50.4	20.2	
			On-Ramp, EB Harrison to EB 20														
2721+42 - 2722 + 00	BUTT JOINT	60.0	16.0	107		0.086	0.20			0.12			13.4	9.0	24.0	9.6	
			OFF-Ramp, EB 20 to WB Harrison														
2727+72 - 2728 + 18		46.0	16.0	82		0.057	0.20			0.10			10.3	6.9	18.4	7.4	
2728+18 - 2729 + 68	TAPER & BUTT JOINT, 3 3/4" - 1 1/4"	150.0	16.0	267		0.186	0.40			0.31			33.6	22.4	60.0	24.0	
			On-Ramp, WB 20 TO NB 39														
2733+18 - 2734 + 00	BUTT JOINT	88.0	16.0	156		0.143	0.50			0.18			19.7	13.1	35.2	14.1	
			On-Ramp DA to WB 20														
2573+40 - 2574 + 90	3 3/4" - 1 1/4", BIT BUTT JOINT	150.0	16.0	267		0.157	0.60			0.31			33.6	22.4	60.0	24.0	
			MISCELLANEOUS AREA TOTALS														
			COLUMN TOTALS														
			PAY ITEM TOTALS														

PLOT DATE = Thu Dec 23 14:32:03 2004  
 FILE NAME = C:\pvc\objects\22125006.dwg  
 PLOT SCALE = 50.0000 / IN.  
 REFERENCE = SHEET#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY