

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WINNEBAGO	317	42
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# CLASS "B" PATCHS

## CLASS B PATCHING

12 FEET LANE WIDTH				44200970	44200974	44200976	4421320	Z0017100	Z0075300	4200120			
STATION	REMARKS	LENGTH OF PATCH		TYPE 2		TYPE 3		TYPE 4		(3W+?L) (feet)	BARS (each)	TIE BARS (each)	PAVEMENT FABRIC (yd <sup>2</sup> )
		LT LANE (feet)	RT LANE (feet)	LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )	LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )	LT LANE (yd <sup>2</sup> )	RT LANE (yd <sup>2</sup> )				
<b>NORTHBOUND 39 - EASTBOUND 20</b>													
2605 + 48		10		13.3						56	20		
2630 + 00		10	10	13.3	13.3					66	40		
2641 + 90		15				20				66	30		20
2642 + 00			15				20			66	30		20
2651 + 60		12	12			16	16			72	40		32
2679 + 20		10	10	13.3	13.3					66	40		
2702 + 60		15	15			20	20			81	60		40
2727 + 00	OFF RAMP		10		13.3					56	20		
<b>SOUTHBOUND 39 - WESTBOUND 20</b>													
2522 + 00		10	10	13.3	13.3					66	40		
2604 + 50		10	10	13.3	13.3					66	40		
2621 + 00		20	20					26.7	26.7	96	60	9	53.3
2634 + 75		10	10	13.3	13.3					66	40		
2643 + 75		10	10	13.3	13.3					66	40		
2651 + 75			10		13.3					56	20		
2655 + 25			10		13.3					56	20		
2668 + 75		15	15			20	20			81	60		40
2680 + 10		10	10	13.3	13.3					66	40		
2694 + 00		10	10	13.3	13.3					66	40		
2721 + 00		10	10	13.3	13.3					66	40		
2721 + 00	OFF RAMP		10		13.3					56	20		
<b>SOUTHBOUND 39 - WESTBOUND 20 AUXILIARY LANE</b>													
2621 + 00	WB AUX LANE		20					26.7		76	30	9	26.7
2634 + 75	WB AUX LANE		10		13.3					56	20		

16 FEET LANE WIDTH													
RAMP BD													
45 + 95	9" CRCP		8		14.2					64	28		
55 + 00	LONGITUDINAL JOINT CRACK		75					133.3		198	98		133.3
59 + 25			30					53.3		108	56		53.3
59 + 70	9" CRCP		30					53.3		108	56		53.3

RAMP DB													
49 + 42	APPR PVT		6		10.7					60	28		
50 + 28			33					58.7		114	56		58.7
51 + 11			89					158.2		226	112		158.2
53 + 21			6		10.7					60	28		
54 + 12			15					26.7		78	42		26.7
56 + 07			15					26.7		78	42		26.7
58 + 84			6		10.7					60	28		
59 + 37			6		10.7					60	28		
60 + 51			244					433.8		536	252		433.8
62 + 95			95					168.9		238	126		168.9
65 + 00	PART DEPTH		10				17.8			68	28		

RAMP AD														
56 + 95	9" CRCP		158					280.9		364	182		280.9	
62 + 85	APPR JT		10				17.8			68	28			
<b>COLUMN TOTALS</b>					<b>133.0</b>	<b>243.2</b>	<b>76.0</b>	<b>111.6</b>	<b>26.7</b>	<b>1447.2</b>	<b>3956.0</b>	<b>2008.0</b>	<b>18.0</b>	<b>1625.8</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY
DATE		

PLOT DATE \* Thu, Jan 06 13:32:52 2005  
 FILE NAME \* c:\pcc\pcc15\2012000\dl2500e.rvt.dgn  
 PLOT SCALE \* 50.0000 / IN.  
 REFERENCE \* REF#