

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	URBAN														
			TOTAL	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE			
			QUANTITY	J000-2A P. C. CONCRETE	SFTY-3N IMPACT ATTEN.	X02B-2A STRUCTURES	X271-2A STRUCTURES	Y007 MINOR STRUCT.	Y030-1E HWY. LIGHTING	Y031-1F SIGNALS	Y077 WETLANDS	Y079 HAZ. WASTE	SFTY-3C BREAKAWAY	Y002-1C TRAFFIC SIGNS			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	18,000	18,000													
28000300	TEMPORARY DITCH CHECKS	EACH	60	60													
28000400	PERIMETER EROSION BARRIER	FT.	9,522	9,522													
28000500	INLET AND PIPE PROTECTION	EACH	17	17													
28100107	STONE RIPRAP, CLASS A4	S. Y.	147	147													
28400100	GABIONS	C. Y.	13	13													
30103000	SHAPING AND GRADING ROADWAY	UNIT	6	6													
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	76,284	76,284													
31200100	STABILIZED SUB-BASE 4"	S. Y.	54,967	54,967													
35100100	AGGREGATE BASE COURSE, TYPE A	TON	1,914	1,914													
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	201	201													
40600200	BITUMINOUS MATERIALS, PRIME COAT	TON	8.0	8.0													
42000216	PORTLAND CEMENT CONCRETE PAVEMENT 7 3/4" (JOINTED)	S. Y.	3,213	3,213													
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	S. Y.	62,250	62,250													
42001165	BRIDGE APPROACH PAVEMENT	S. Y.	339	339													
42001300	PROTECTIVE COAT	S. Y.	112,764	112,764													
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	S. Y.	1,223	1,223													
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	S. Y.	4,616	4,616													
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT (7 INCH)	S. Y.	1,550	1,550													
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	S. F.	8,063	8,063													
44000100	PAVEMENT REMOVAL	S. Y.	33,885	33,885													