

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	7
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	100% STATE														
			URBAN														
			TOTAL	J000-2A	SFTY-3N	X028-2A	X271-2A	Y007	Y030-1E	Y031-1F	Y077	Y079	SFTY-3C	Y002-1C			
QUANTITY	P. C. CONCRETE	IMPACT ATTEN.	STRUCTURES	STRUCTURES	MINOR STRUCT.	HWY. LIGHTING	SIGNALS	WETLANDS	HAZ. WASTE	BREAKAWAY	TRAFFIC SIGNS						
44000200	DRIVEWAY PAVEMENT REMOVAL	S. Y.	1,465	1,465													
44000500	COMBINATION CURB AND GUTTER REMOVAL	FT.	5,699	5,699													
44000600	SIDEWALK REMOVAL	S. F.	12,296	12,296													
44213200	SAW CUTS	FT.	498	498													
48100100	AGGREGATE SHOULDERS, TYPE A	TON	1,348	1,348													
48300100	PORTLAND CEMENT CONCRETE SHOULDERS, 6"	S. Y.	467	467													
48300410	PORTLAND CEMENT CONCRETE SHOULDERS, 9 1/2"	S. Y.	20,703	20,703													
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2													
50105200	REMOVE EXISTING CULVERTS	EACH	3	3													
50200100	STRUCTURE EXCAVATION	C. Y.	448					448									
* 50200400	ROCK EXCAVATION FOR STRUCTURES	C. Y.	5						5								
50300225	CONCRETE STRUCTURES	C. Y.	228.6					228.6									
50300255	CONCRETE SUPERSTRUCTURE	C. Y.	491.9	4.3				487.6									
50300260	BRIDGE DECK GROOVING	S. Y.	1,523					1,523									
50300300	PROTECTIVE COAT	S. Y.	1,739					1,739									
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L. SUM	1					1									
50500505	STUD SHEAR CONNECTORS	EACH	4,563					4,563									
50800105	REINFORCEMENT BARS	POUND	171,290				76,280		95,010								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	161,270					161,110	160								
51100100	SLOPE WALL 4 INCH	S. Y.	852					852									
51201500	FURNISHING STEEL PILES HP 10 X 57	FT.	1,851					1,851									

*SPECIALTY ITEM