

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE		
				URBAN	J000-2A	SFTY-3N	X028-2A	X271-2A	Y007	Y030-1E	Y031-1F	Y077	Y079	SFTY-3C	Y002-1C
				QUANTITY	P. C. CONCRETE	IMPACT ATTEN.	STRUCTURES	STRUCTURES	MINOR STRUCT.	HWY. LIGHTING	SIGNALS	WETLANDS	HAZ. WASTE	BREAKAWAY	TRAFFIC SIGNS
51202700	DRIVING STEEL PILES	FT.	1,851					1,851							
51203500	TEST PILE STEEL HP 10 X 57	EACH	3					3							
51204600	METAL SHOES	EACH	48					48							
51500100	NAME PLATES	EACH	2			1	1								
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2											
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2	2											
54002020	EXPANSION BOLTS 3/4 INCH	EACH	32					32							
54003000	CONCRETE BOX CULVERTS	C. Y.	997.6			480.9		516.7							
54020303	PRECAST CONCRETE BOX CULVERT 3' X3' (M273)	FT.	50	50											
54020502	PRECAST CONCRETE BOX CULVERT 5' X2' (M273)	FT.	146	146											
542A0223	PIPE CULVERTS, CLASS A, TYPE 1, 18"	FT.	44	44											
542A1060	PIPE CULVERTS, CLASS A, TYPE 2, 15"	FT.	50	50											
542A3391	PIPE CULVERTS, CLASS A, TYPE 5, 36"	FT.	206	206											
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	12	12											
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3											
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3											
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2											
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	4											
54215547	METAL END SECTIONS 12"	EACH	22	22											
54215550	METAL END SECTIONS 15"	EACH	2	2											
54248510	CONCRETE COLLAR	C. Y.	0.22	0.22											