

SUMMARY OF QUANTITIES

F.A.P. SHEETS	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEMS	UNIT	TOTAL	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	93% STATE 7% CITY OF ROCKISLAND	100% STATE	100% STATE	100% STATE
				J000-2A	SFTY-3N	X028-2A	X271-2A	Y007	Y030-1E	Y031-1F	Y031-1F	Y079	SFTY-3C	Y002-1C
				QUANTITY	P. C. CONCRETE	IMPACT ATTN.	STRUCTURES	STRUCTURES	MINOR STRUCT.	HWY. LIGHTING	SIGNALS	HAZ. WASTE	BREAKAWAY	TRAFFIC SIGNS
*81400300	DOUBLE HANDHOLE	EACH	3							2	1			
*81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FT.	15,568							10,312	4084	1172		
*81600215	UNIT DUCT, 2*8XLP, 1*8 XLP GROUND 3/4" POLYETHYLENE	FT.	11,957							11,957				
*81600415	UNIT DUCT, 2*4XLP, 1*4 XLP GROUND 1" POLYETHYLENE	FT.	860							860				
*81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FT.	4,302								2,582	1,800		
*81702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FT.	3,472							3,472				
*82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	83							83				
*82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	1								1			
*82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	9								6	3		
*82500540	LIGHTING CONTROLLER CB - RCS - 100 - 480	EACH	1							1				
*83002600	LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. DAVIT ARM	EACH	49							49				
*83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FT.	136							136				
*83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	49							49				
*83800650	BREAKAWAY DEVICE, COUPLING, SS SCREEN	EACH	196										196	
*85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	3								2	1		
*86000100	MASTER CONTROLLER	EACH	1								1			
*86400100	TRANSCEIVER-FIBER OPTIC	EACH	3								2	1		
*87100160	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5, 24F	FT.	1,968								959	1,009		
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FT.	7,901								5,663	2,238		
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FT.	762									762		

* SPECIALTY ITEMS