

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	58
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

*2001291 VALVE GATE, 6" MJRW & BOX	EACH	
52ND AVENUE		
82.17' LT. STA. 1173+35.63		1
57.25' LT. STA. 213+49.89		1
40.11' LT. STA. 217+99.87		1
RELOCATED THIRD STREET		
31.95' RT. STA. -0+66.54		1
22.81' RT. STA. 3+78.88		1
26.01' LT. STA. 10+48.49		1
TOTAL	6	
*2001292 WATER MAIN COUPLING 12"	EACH	
52ND AVENUE		
26.14' LT. STA. 218+53.45		1
TOTAL	1	
*2001293 DUCTILE IRON SLEEVE, 12"	EACH	
TRINITY DRIVE		
46.48' RT. STA. 1+02.07		1
TOTAL	1	
*2001294 DUCTILE IRON SLEEVE, 8"	EACH	
JOHN DEERE ROAD		
RT. STA. 409+00-410+00		3
TOTAL	3	
*2001295 DUCTILE IRON WATER MAIN 8" IN STEEL CASING	FT.	
JOHN DEERE ROAD		
RT. STA. 409+00-410+00		75
TOTAL	75	